EVANS WOLFENDEN
PARTNERSHIP

Mr W P Jurkokc
Penrallt
Russell Street
Cefn Mawr
Wrexham
LL14 3BL

Our Ref: EWP/0566/L2

Date: 7 December, 2005

Dear Sirs,

Re: **Proposed Dwelling to Land Adjacent to Bron y Graig, Cefn Mawr, Wrexham – Foundation Advice**

Further to our letter of 27th October and subsequent discussions with Joanne Wooding of Wrexham County Borough Council, we enclose three copies of drawing EWP0566/s(20)L001 and calculation sheets EWP/0566/1-13 inclusive. Two copies need to be submitted to Building Control by you.

Preliminary contamination test results in respect of pH and sulphates returned the following:

	ECoS REPORT NO.	053214i	e0113	
	DATE ISSUED	01/12/05		
	BH/TP	TP1	TP2	TP3
	SAMPLE DEPTH	0.50m	0.50m	0.50m
	YOUR ID REF.			
	SAMPLE TYPE			
	DATE SAMPLED			
	RECEIPT DATE	22/11/05	22/11/05	22/11/05
	OUR REF.	S0527176	S0527178	S0527179
	MATRIX	Soil	Soil	Soil
pH	N/A	4.7	7.9	6.2
Sulphate (water soluble)	g/l SO4	0.06	0.043	0.107

Based on these results, we consider that RC40 concrete to BS8500 will be suitable with no additional precautions required.

We also enclose our invoice for the works to date. We trust that the above is sufficient for your current requirements, but please don not hesitate to contact this office should you require any additional information.

Yours Faithfully,

John Evans
For Evans Wolfenden Partnership Ltd

EVANS WOLFENDEN PARTNERSHIP LTD
CONSULTING ENGINEERS
Directors – Mr. John Evans & Mr. Graham Wolfenden
FIRST FLOOR, 27 PRINCES DRIVE, COLWYN BAY, CONWY LL29 8HT
e-mail: info@ewpeng.co.uk, Tel 01492 533721, Fax 01492 532252
LTD Company No. 5438374 VAT Registration Number 800 7273 60