Title : Schedule of Internal materials & finishes

Date : 29.11.24

Church Section

Item	Existing	Proposed
Ceiling	Lathe and plaster	Insulation laid over original lathe and plaster with new plaster board & paint finish
Floor	Timber Floor	Timber floor levelled and relayed
Doors	Original to remain	New timber doors in new timber stud walls
Windows	Overhauled & Painted and see Secondary Glazing Datasheet	2 new metal windows on first floor. Proposed Internal window frame colour : White
Internal Walls	Retained & Decorated	New internal walls made of Timber & Plasterboard & Painted

School Section

Item	Existing	Proposed
Ceiling	Lathe and plaster	Insulation laid over original lathe and plaster with new plaster board & paint finish
Floor	Concrete solid Floor	Retained floor
Doors	Original to remain	New timber doors in new timber stud walls
Windows	Overhauled & Painted and see Secondary Glazing Datasheet	No new windows proposed
Internal Walls	Retained & Decorated	New internal walls made of Timber & Plasterboard & Painted

1971 extension

Item	Existing	Proposed
Ceiling	Damp Plasterboard and painted	Insulation, plasterboard and painted
Floor	Concrete solid Floor	Retained floor
Doors	Replace some 1970's doors	New timber doors
Windows	Replace no. 2 1970's timber windows	No. 2 new timber windows on ground floor. Proposed Internal widow frame colour : White
Internal Walls	Retained & Decorated	No new walls proposed