MEMORANDUM

From:	Chief Officer, Environment & Technical	**To:**	Chief Officer Economy & Planning
		FAO::	Alan Wells
Our Ref:	ET/DC/PP/P/2024/1657	**Your Ref:**	P/2024/1657
Date:	13/01/2025		

TOWN AND COUNTRY PLANNING ACT 1990

PROPOSAL: CODI IARD DDAL DAN DO / ERECTION OF A COVERED HOLDING YARD
LOCATION: YEW TREE FARM, LLAY ROAD, BURTON, ROSSETT, WREXHAM, LL12 0HT

I refer to your consultation / email dated 19/12/2024 in respect of the above.

The proposed development site is located on a rural, classified road subject to a 40mph speed limit.

Any proposed / existing access would normally be required to provide visibility splays of 2.4 x 120m in both directions measured to the nearside edge of the adjoining highway in accordance with TAN 18.

Visibility from the existing access (7.4m wide) is inadequate in both directions in that the required splays would need to cut across 3rd party land. Current visibility splays from this access are approximately 2.4 x 10m to the west and 2.4 x 43m to the east measured to the nearside edge. However, this is an existing access and the proposed development for a covered holding yard is considered unlikely to result in any significant increase in vehicle movements.

The LHA therefore advises you that they do not intend to make any recommendations on highway grounds.

Supplementary Notes

The applicant's attention should be drawn to item nos. 1, 2, 3, 4 & 5 of the supplementary notes.

Note to Applicant:

Public Footpath No.35 - Burton passes through the development site and should not be interfered with. I would strongly recommend that the applicant liaise with our Public Rights of Way Section to discuss the proposed development. Please contact Mr. Sean Hanratty on Tel: 01978 729761.



On behalf of Chief Officer, Environment & Technical

Supplementary Notes

The applicant's attention should be drawn to item nos. 1, 2, 3, 4 & 5 of the supplementary notes.

Appendix

Highways Development Control Standard Advisory Note

In the interests of maintaining highway safety, and to avoid obstruction of the public highway (in contravention of the Highways Act), The Applicant is advised to coordinate with the highway authority at highwayroadworks@wrexham.gov.uk in advance of commencement of the development/works with respect to:

1. *Skip, scaffolding, hoarding or A frame/signage (Permit required for these items, if on the public highway);*
2. *Use of a parking space for a set down/delivery area;*
3. *Record a dilapidation survey of the adjacent carriageway prior to commencement (to avoid being ask to repair damage by the Applicant whilst carrying out their works);*
4. *If any lane closure or obstruction of the highway is required for a crane or similar;*
5. *Protection against dust and debris blowing onto the public highway*
6. *Construction traffic parking locally avoiding nuisance to others;*
7. *If the Applicant's scope of work includes new apparatus in the highway, such as new mains services then a Section 50 licence will be required. Insurances and demonstration of competency to carry out works in the public highway will be required.*
8. *Lowering of kerbs or minor pavement alterations require Section 184 agreement. Insurances and demonstration of competency to carry out works in the public highway will be required.*
9. *A section 278 agreement works agreement is required for more significant alterations to the existing highway*
10. *Any temporary works affecting traffic lights, [pedestrian/cycle road crossings, or bus stops require pre-planning and permits;*
11. *For applications with a private driveway (either existing or proposed) connecting onto the public highway, the following conditions of approval apply:*

    - *No surface water from the applicants site should be allowed to drain onto the public highway,*
    - *The first 5m* minimum (for residential property) should be hard paved, avoiding gravel or loose chippings form spreading.*
    - *No gate should be built in a location where it would result in a car obstructing the highway whilst being unlocked, and it should not swing out and over a pavement or any other part of the highway.*

    **The hard paved length and set back if required is subject to the applicants proposed vehicular length*

The applicants should allow a minimum of 4 weeks' notice for any of the above standard requirements, and 6-8 weeks for lane closures & road closures (lead times may change without notice subject to workload and complexity). Any works involving Trunk roads should be coordinated separately and directly with the North & Mid Wales trunk Road Agency. For larger sites with a significant impact upon the highway, a Construction Traffic Management Plan will be required.