
Project Title	Wrexham BC - Ysgol Morgan Llwyd	Project Number	24049-D1

Finishes Schedule

Item	Material	Colour	Image
External			
Roof	Kingspan insulated roof sheets with profiles plastisol covered steel sheet outer layer.	Albatross	
Copings/ Fascias	Colorcoated profiled steel	Anthracite Grey RAL 7016	RAL 7016
Rainwater Goods	uPVC gutters, 61mm square downpipes	Black RAL 9005	RAL 9005
Ext Wall Panels (composite)	Wernick composite wall panels with external finish of leather grain plastisol	Anthracite Grey RAL 7016	RAL 7016
Skirt	Solway	Black RAL 9005	RAL 9005
External finish	JUB render	White RAL 9010	RAL 9010
	JUB render	Burgundy RAL 3004	RAL 3004
Windows	Powdercoated Aluminium	Anthracite Grey RAL 7016	RAL 7016
	Cill (Int) - Painted MDF Cill board with P/Board reveals	Anthracite Grey RAL 7016	
	Nylon Coated Handle	TBC	
Ext Doors	Powdercoated Aluminium	Anthracite Grey RAL 7016	RAL 7016
	2 x double glazed panels	Clear	
	3 Point panic lock and touch bar to fire escape doors.	TBC	

Status:	**issued for approval**		
Client:	Wrexham - Ysgol Morgan Llwyd		
Design:	SL	Technical:	P03
Date:	11/02/2025_SL	Rev.	