## PLANT SCHEDULE

NOTE: This schedule does not include Plants contained within Landscape Areas and Hedgerows

| Category | Form | Quantity | Latin Name | Girth | Height | Clear Stem | Other |
|---|---|---|---|---|---|---|---|
| Tree | Standard | 6 | Acer campestre | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 7 | Acer campestre | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 8 | Alnus glutinosa | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 2 | Alnus glutinosa | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 4 | Betula pendula | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 2 | Carpinus betulus | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 6 | Corylus avellana | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 11 | Crataegus monogyna | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 4 | Crataegus monogyna | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 2 | Prunus avium | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 2 | Prunus avium | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 1 | Prunus padus | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 4 | Pyrus ' Chanticleer' | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 13 | Quercus robur | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 3 | Quercus robur | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 1 | Salix caprea | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 1 | Salix fragilis | 8-10cm | 2.5-2.75m | 2m | Bare Root |
| Tree | Standard | 2 | Sorbus aucuparia | 6-8cm | 1.5-1.75m | | Bare Root |
| Tree | Standard | 5 | Sorbus aucuparia | 8-10cm | 2.5-2.75m | 2m | Bare Root |

## LANDSCAPE AREAS

| Area Name | Percent | Quantity | Latin Name | Scheduled Size | Rate/Spacing |
|---|---|---|---|---|---|
| Aquatic Marginal Mix | | 0 | | | |
| N/A | 15 | 84 | Centaurea nigra | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 10 | 54 | Eupatorium cannabinum | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 3 | 16 | Filipendula ulmaria | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Caltha palustris | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Achillea ptarmica 'Perrys White' | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 12 | 65 | Angelica gigas | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 3 | 16 | Apium nodiflorum | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 6 | 32 | Silene flos-cuculi | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 15 | 84 | Ranunculus acris 'Flore Plena' | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Vicia cracca | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Succisa pratensis | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Lycopus europaeus | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 5 | 28 | Lotus pedunculatus | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 3 | 16 | Pulicaria dysenterica | 2 ltr c/g | 6.25 Plants/sq m |
| N/A | 3 | 16 | Mentha aquatica | 2 ltr c/g | 6.25 Plants/sq m |
| EM1 Basic General Purpose Meadow Mixture | | 0 | | | |
| N/A | 100 | 7979 | Basic General Purpose Meadow Mixture | Seeds | 1 Plants/sq m |
| Euonymus Hedge 1 | | 0 | | | |
| N/A | 100 | 999 | Euonymus 'Jean Hugues' | 3 ltr c/g | 0.3 Meters on center |
| Native Hedging Mix 1 | | 0 | | | |
| N/A | 5 | 96 | Ilex aquifolium | 3 ltr c/g | 4 Plants/sq m |
| N/A | 5 | 96 | Rosa canina | 3 ltr c/g | 4 Plants/sq m |
| N/A | 10 | 189 | Viburnum opulus | 3 ltr c/g | 4 Plants/sq m |
| N/A | 5 | 96 | Alnus glutinosa | 3 ltr c/g | 4 Plants/sq m |
| N/A | 20 | 381 | Corylus avellana | 3 ltr c/g | 4 Plants/sq m |
| N/A | 10 | 189 | Frangula alnus | 3 ltr c/g | 4 Plants/sq m |
| N/A | 5 | 96 | Sambucus nigra | 3 ltr c/g | 4 Plants/sq m |
| N/A | 40 | 762 | Crataegus monogyna | 3 ltr c/g | 4 Plants/sq m |
| Native Thicket Mix | | 0 | | | |
| N/A | 20 | 1589 | Corylus avellana | 3 ltr c/g | 1 Plants/sq m |
| N/A | 10 | 793 | Cornus sanguinea | | 1 Plants/sq m |
| N/A | 5 | 397 | Acer campestre | | 1 Plants/sq m |
| N/A | 10 | 793 | Ligustrum vulgare | | 1 Plants/sq m |
| N/A | 10 | 793 | Viburnum lantana | 3 ltr c/g | 1 Plants/sq m |
| N/A | 10 | 793 | Salix caprea | | 1 Plants/sq m |
| N/A | 5 | 397 | Rosa canina | 3 ltr c/g | 1 Plants/sq m |
| N/A | 10 | 793 | Euonymus europaeus | 3 ltr c/g | 1 Plants/sq m |
| N/A | 10 | 793 | Crataegus monogyna | 3 ltr c/g | 1 Plants/sq m |
| N/A | 5 | 397 | Ilex aquifolium | 3 ltr c/g | 1 Plants/sq m |
| N/A | 5 | 397 | Hippophae rhamnoides | | 1 Plants/sq m |
| Ornamental Planting 2 | | 0 | | | |
| N/A | 100 | 675 | Anemanthele lessoniana | 2 ltr c/g | 4 Plants/sq m |
| Ornamental Planting 3 | | 0 | | | |
| N/A | 100 | 144 | Sarcococca hookeriana var. humilis | 3 ltr c/g | 4 Plants/sq m |
| Ornamental Planting 4 | | 0 | | | |
| N/A | 100 | 144 | Sarcococca hookeriana 'Winter Gem' | 3 ltr c/g | 4 Plants/sq m |
| Ornamental Planting 5 | | 0 | | | |
| N/A | 15 | 306 | Viburnum tinus | 3 ltr c/g | 0.5 Meters on center |
| N/A | 25 | 508 | Spiraea 'Shirobana' | 3 ltr c/g | 0.5 Meters on center |
| N/A | 20 | 408 | Hebe rakaiensis | 3 ltr c/g | 0.5 Meters on center |
| N/A | 20 | 408 | Lonicera ligustrina var. pileata | 3 ltr c/g | 0.5 Meters on center |
| N/A | 10 | 565 | Pennisetum alopecuroides | 2 ltr c/g | 0.3 Meters on center |

## LANDSCAPE AREA SUMMARY

| Area Name | Area m2 |
|---|---|
| Aquatic Marginal Mix | 87.819 |
| | 0 |
| EM1 Basic General Purpose Meadow Mixture | 7977.943 |
| | 0 |
| Euonymus Hedge 1 | 89.811 |
| | 0 |
| Native Hedging Mix 1 | 475.428 |
| | 0 |
| Native Thicket Mix | 7939.375 |
| | 0 |
| Ornamental Planting 2 | 168.502 |
| | 0 |
| Ornamental Planting 3 | 36.158 |
| | 0 |
| Ornamental Planting 4 | 36.158 |
| | 0 |
| Ornamental Planting 5 | 508.513 |
| | 0 |

### General Notes

1. Do not scale from drawing unless it is a specified setting out plan and you have confirmed it is printed to scale.
2. All dimensions and levels shown must be confirmed by contractors prior to the commencement of construction works.
3. All measurements must be checked on site.
4. Drawings are to be read in conjunction with all other relevant plans, design packs and schedules.
5. All work must comply with the current building regulations.
6. No materials used or methods of workmanship to be employed that do not conform to the current relevant British Standard and Code Of Practice.
7. All plants and materials are subject to avialabilty at time of ordering.
8. Topsoils to be placed to 450mm overall depth in shrub and herbaceous areas and 600mm in tree pits and hedge trenches. Soils should be placed in 150mm layers, firming as you go, over compaction free, well draining subsoil.

| | | | |
|---|---|---|---|
| 26/11/2024 | 2 | CB | Post & Rail fence changes |
| 21/11/2024 | 1 | | Issue |

| Date | Original size | Scale | Drawn by | Checked by | Rev |
|---|---|---|---|---|---|
| 14/02/2025 | A3 | 1:350 | CB | JK | V3 |

Drawing no: 1059-01-NLD.151 Bryn Lane South

Status: S4

Drawing Title: Soft Landscape Design

Sheet Name: Plant Schedule

Location: Bryn Lane South, Wrexham

Client name: Net Word Sport

Nicholsons is a trading name of Nicholsons Nurseries Ltd. The Park, North Aston, Bicester, Oxfordshire. OX25 6HL.
T +44 (0)1869 340342 www.nicholsonsgb.com | Company No. 04820053

NICHOLSONS