

APPENDIX 8.5

OPERATIONAL NOISE LEVELS

Plant	Measured Sound Pressure Levels LAeq dB	Assumed Sound Power Levels dBA
HGV movement on access road	75 @ 10m	103
HGV movement into parking area	72 @ 10m	100
HGV Tick-over	63 @10m	91
Transformer	63 @ 2m	77
Log loader	78 @ 10m	106