Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331, 4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-63 	G48	Stair 4	OVERHAUL	TYPE 1 Existing Fire door to be retained	Single	Y	N/A	N/A	825	2042	43	Paint TBC	TBC	FD30S	N/A	N/A	ED-02 TO BE REVIEWED	Fire Remedial Works Extensive damage has occurred to the existing door frame at low level. This is to be repaired/replaced as required by a fire door repair specialist. Existing Ironmongery 3 x hinges 1 x o/head closer 2 x foot plates 1 x pushplate 1 x pull handle 2 x 'FDKS signs' - remove and make good 3 x directional signs - remove and make good Ironmongery Notes New eurolock, thumbturn/ handle and escutcheons New Welsh/ English fire signage
DG-65	G49	Store	NEW	TYPE 3C	Single	N	2100	910	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-30	Ironmongery Notes Digilock required
DG-66	G41	Office	NEW	TYPE 3A	Single	Y	2100	1010 (TBC On Site)	2040	920 (Min)	43	Paint	TBC	FD30S	Rw30dB	N/A	X IRON-MONGERY REQUIRED	Ironmongery Notes Previously was ND-05, but not included in current issue of ironmongery schedule. Check whether digilock required. (Review with WCBCc)
DG-68 	G40	Store	OVERHAUL TBC	TYPE 1 Existing modern fire door	Single	N	N/A	N/A	2051	820	43	Paint TBC	TBC	FD30 NOTE: FE TO REVIEW XTG DOOR	N/A	N/A	ED-14 TO BE REVIEWED	FIRE RATING ASSUMED - AWAITING FE's CONFIRMATION Do not undertake works until FE response received Existing ironmongery 3 x hinges (check on site) o/h closer Latch 2 x lever handles Fire Signage - remove and make good Seals in door frame Ironmongery Notes Change eurolock (suiting TBC) New bilingual fire signage (Square/ size to match existing)

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-71	G15	Gender Neutral WC	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-06	
DG-72	G17	Gender Neutral WC	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-06	
DG-73	G19	Gender Neutral WC	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-06	
DG-74	G58	Gender Neutral WC	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-06	
DG-75	G57	Cleaners Store	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-31	ALLGOOD NOTE: Same door spec as ND-07
DG-76	G37	Glazed Link	NEW	TYPE 3B	Leaf and Half	Y	2100	1450	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-08 TO BE REVIEWED	ACCESS CONTROL NEEDS TO BE INCLUDED TO RELEASE AS FIRE ALARM SOUNDS (WCBC identify no lock, but access control - provide ironmongery options) DG-76 had ND-08 ironmongery DF-42 hasND-21 ironmongery both need access control adding and amendment

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-77	G20	Accesible WC	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	**Paint**	TBC	N/A	RW30dB	N/A	ND-09 TO BE REVIEWED	EURO CYLINDER PROVIDED - EXTERNAL WINDOW 926 mm minimum door leaf required NOTE: DOOR TO BE INSTALLED OUTWARD OPENING
DG-78	G18	Family Room	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	**Paint**	TBC	N/A	RW30dB	N/A	ND-10 TO BE REVIEWED	926 mm minimum door leaf required CHECK IF DOOR CAN BE INWARD OPENING
DG-84	N/A	Changing Cubicle	NEW	NON STANDARD DOOR TYPE	Single	N	2100	810	N/A	750	N/A	**Paint**	TBC	**N/A**	N/A	N/A	X	IPS CUBICLE MANUFACTURER TO PROVIDE IRONMONGERY Door and partition not full height.
DG-85	G23	Fumiture Store	NEW	TYPE 3B	Leaf and Half	N	2100	1550	N/A	N/A	N/A	**Paint**	TBC	**FD30S**	N/A	N/A	ND-12/A	926 + 450 door leafs Suiting TBC
DG-86	G59	Exhibition Store	NEW	TYPE 3B	Leaf and Half	N	2100	1460	N/A	N/A	N/A	**Paint**	TBC	**FD30**	N/A	N/A	ND-12 TO BE REVIEWED	DOOR AND FRAME TO BE FLUSH WITH GALLERY LINING Review lever handles on gallery side 926 + 450 door leafs
DG-87	G30	Plant	NEW	TYPE 3C	Single	N	XTG (TBC On Site)	XTG (TBC On Site)	2070 (ASSUMED)	680 (ASSUMED)	45 (ASSUMED)	**Paint**	TBC	**FD30**	N/A	N/A	ND-13 TO BE REVIEWED	Retain existing architraves CHECK IRONMONGERY Deadlock vs Digilock

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-88 	G01	Welcome	OVERHAUL	TYPE 1 Glass sliding door with pocket	Sliding	N	N/A	N/A	2165 SO	1250 SO	32	Glass	N/A	N/A	N/A	N/A	X	MEP Engineer to confirm viability of door retention Refer to MEP drawings for supply information
DG-89 	G01	Welcome	OVERHAUL	TYPE 1 Glass sliding door with pocket	Sliding	N	N/A	N/A	TBC ON SITE	TBC ON SITE	TBC ON SITE	Glass	N/A	N/A	N/A	N/A	X	MEP Engineer to confirm viability of door retention Refer to MEP drawings for supply information
DG-90	G36	Building Gallery	NEW	TYPE 2A	Single Swing	N/A	XTG Site Demo TBC	XTG Site Demo (926 leaf to be achieved)	N/A	N/A	N/A	PCC Aluminium	TBC	FD30S	DB30	N/A	X	IRONMONGERY ASSUMED TO BE PROVIDED BY DOOR SUPPLIER - to match Allgood Automatic Door Wall mounted, Push Pad to open both sides
External Doors																		
DG-06  	G46	Stair 2	OVERHAUL	TYPE 1 Existing Historic door to be retained	Double Leaf	N	N/A	N/A	LHS: 2060 RHS: 2035	LHS: 550 RHS: 565	LHS: 55 RHS: 55	Paint	TBC	N/A	N/A	N/A	OH-03 TO BE REVIEWED	Repair Notes Repair existing door and frame, make good where ironmongery removed. Agree scope with AABC before undertaking works. Existing Ironmongery External: 2 x 2 x 130mm (h) hinges - retain Perspex in front of stained glass - remove, clean, refix Fire exit keep clear sign - remove Letterbox - remove and make good styal Internal: Turn to open sign - remove and make good Thumbturn - remove and make good Fire exit sign - remove and make good High/low level bolt on RHS leaf - retain Lever handle + lock internal and external - remove and make good – Ironmongery Notes Digilock / electronic access (TBC) TO RELEASE AT FIRE ALARM - WCBC to confirm access requirement Eurolock/ latch/ excutcheons Lever handle/ thumbturn ?

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC



LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-08 	G10	Plant 1	OVERHAUL	TYPE 1 Existing Historic door to be retained	Single	N	N/A	N/A	2050	850	55	Paint	TBC	N/A	N/A	N/A	OH-05 TO BE REVIEWED	Repair Notes Existing historic FLB door to be retained and repaired. Remove defective sections of frame and splice in new sections of timber to match exactly. Remove any defective sections of the door leaf frame and boarding and slice in new sections of timber to match exactly. Make good where ironmongery removed. Prime and undercoat all new sections of timber. Existing Ironmongery: Existing Hinges - check condition/ remove Lock and latch set - remove 2no. Lever handles - remove Ironmongery Notes 3 x hinges Eurolock and escutcheon/ pull (Suiting TBC)
DG-21 	G11	Special Exhibition Galleries / Activites	OVERHAUL	TYPE 1 Existing Historic door to be retained	Single	N	N/A	N/A	2120	1020	72	Paint	TBC	N/A	N/A	N/A	X	Repair Notes Existing historic FLB door to be retained and repaired. Door and frame to be brought forward in the opening to allow blockwork to be installed behind. Keep a minimum of 100mm recess. Remove defective sections of frame and splice in new sections of timber to match exactly. (Approx 450mm, diagonal splice) Remove any defective sections of the door leaf frame and boarding and slice in new sections of timber to match exactly. (Note: approx of minimum of 200mm on the nboarding and the bottom rail needs replacing - this should be tenoned, confirm proposed methodology before proceeding.) Make good where ironmongery removed. Fix door in frame. Any fixings to be recessed and pelleted. Prime and undercoat all new sections of timber. Existing Ironmongery Poster frame - remove 3x130mm (h) hinges - remove Pull handle - remove Horizontal bolt lock with padlock - remove Low level horizontal bolt lock (broken) - remove

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-26 EXISTING  PROPOSED 	G13	Exhibition Prep	RECLAIMED FROM SITE	TYPE 5 Historic door leaf to be reclaimed from site from DF-19	Single	N	XTG (Site dim)	XTG (Site dim)	XTG 1985 RECLAIMED 1989	XTG 814 RECLAIMED 807	XTG TBC RECLAIMED 38	Paint	TBC	N/A	N/A	SH	X IRON-MONGERY REQUIRED	Repair Notes Remove redundant ironmongery and make good door and frame. Agree scope of work with AABC prior to undertaking Existing Ironmongery Suffolk latch and receiver - remove and make tood door and frame - re-use to repair elsewhere ((DF-13?) 2 x hinges (assumed) - remove and make tood door and frame Ironmongery Notes 3 x hinges Eurolock and override (final exit door)
DG-27	G14	Plant	NEW	TYPE 4 SR3 Door	Single	N	XTG	XTG	XTG 1985	XTG 814	N/A	PC Steel Door	TBC	N/A	N/A	N/A	X	Installation Notes Assumed that the ironmongery is supplied by the door fabricator. Final exit door Hinges/Lock/Levers/Thumb Turn Locks to be suited with other SR3 plant room doors
DG-38 EXISTING  PROPOSED 	G24	Learning and Community Hub 1	RECLAIMED FROM SITE RETAIN FRAME & FANLIGHT	TYPE 5 Historic door leaf to be reclaimed from site from DF-03	Single with Fanlight	N	N/A	N/A	XTG 1955 RECLAIMED 1955	XTG 905 RECLAIMED 1010	XTG 47 RECLAIMED 65	Paint	TBC	N/A	N/A	N/A	OH-10 TO BE REVIEWED	Repair Notes Remove existing door and retain frame, make good frame where redundant ironmongery removed. Remove glass from fanlight and install metal louvre with insect mexh as per MEP drawings. Make good reclaimed door where redundant ironmongery removed. Agree scope of work with AABC prior to undertaking. Existing Ironmongery (DF-03) 3 x hinges - retain O/H closer - remove and make good 2 x oval knobs - retain and adjust Rimlock/ nigtlatch - retain Ironmongery Notes Eurolock/ latch Lever handle/ thumbturn vs panic bar - needs to work with existing ironmongery Renew FE signage

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																		
DG-55 	G45	Stair 1	OVERHAUL	TYPE 1 Existing Historic door to be retained	Double Leaf	N	N/A	N/A	2220	LHS: 637+15 RHS?	55	Paint	TBC	N/A	N/A	N/A	OH-10 TO BE REVIEWED	Repair Notes Make good where any previous ironmongery has been removed. Existing Ironmongery Internal: 2x 130mm(h) hinges - retain Horizontal bolt and receiver - retain High/low level vertical bolts on RHS door (internally) - retain, clean off paint 2x lever handles on LHS door (internally) - remove, make good door Turn to open sign - remove Thumbturn and keylock - remove and make good doors External: Fire exit keep clear sign -remove and make good Ironmongery notes Eurolock/ thumbturn/ Escutcheons Renew fire signage - final exit sign
DG-59 	G01	Welcome	NEW	PATENT GLAZING SYSTEM	Glazed Single	N/A	REFER TO FABRICATION DRAWINGS FOR DETAILS					PC Aluminium Door	TBC	N/A	N/A	N/A	X	REFER TO FABRICATOR'S DRAWINGS AND INFORMATION FOR DETAILS Fabricator to provide door ironmongery Automatic door PIRs internally Push pad externally
DG-60 	G01	Welcome	NEW	PATENT GLAZING SYSTEM	Glazed Double Leaf	N/A	REFER TO FABRICATION DRAWINGS FOR DETAILS					PC Aluminium Door	TBC	N/A	N/A	N/A	X	REFER TO FABRICATOR'S DRAWINGS AND INFORMATION FOR DETAILS Fabricator to provide door ironmongery Automatic doors to operate on PIRs on both sides
DG-64 	G48	Stair 4	OVERHAUL TBC	TYPE 1	Single	N	N/A	N/A	2100	900	55	Paint	TBC	N/A FINAL EXIT	N/A	N/A	ED-01 TO BE REVIEWED	Existing final exit door to be retained Make good door and frame where redundant ironmongery removed. Ironmongery Notes Welsh/ English fire signage Deadlock - WCBC to confirm
DG-67	G42	Plant 2	NEW	TYPE 4 SR3 Door	Double Leaf	N	2100 TBC	1820 TBC	N/A	N/A	N/A	PPC	TBC	FD30	N/A	N/A	X	Installation Notes Assumed that the ironmongery is supplied by the door fabricator: Final exit door Hinges/Lock/Levers/Thumb Turn Locks to be suited with other SR3 plant room doors NOTE: Louvred doors to MEP Engineer's ventilation requirements

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING											DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																			
DG-80 EXISTING  PROPOSED 	G24	Learning and Community Hub 1	RECLAIMED FROM SITE	TYPE 5 Historic door leaf to be reclaimed from site	Single	N	SITE DIM 2040	SITE DIM 985	RECLAIMED 2045	RECLAIMED 882	RECLAIM 65	PAINT	TBC	N/A	N/A	N/A	OH-15 WCBC TO CONFIRM PANIC BOLT	Repair Notes Original door opening, currently a window, to be reconverted to a door opening with a reclaimed door and frame. Repair door and frame where redundant iron mongery required. Review scope of works with AABC before undertaking. Existing Ironmongery 3 x 100mm hinges - retain 2 x bolts and receivers (150mm) - retain 1no. historic escutcheon - retain Ironmongery to be reviewed IronmongeryNotes Final exit door - Panic bolt provided Eurolock/ Deadlock/ escutcheons
DG-70		NE Plant	NEW	N/A	Single Leaf	N	2500 TBC	1200 TBC	N/A	N/A	N/A	TBC	TBC	N/A	N/A	N/A	X	Refer to Landscape Architect's information for specification of 2.5m high timber SR3 rated security gate and fence NOTE Final location and setting out requires coordination with plant layouts
DG-79		SW Plant	NEW	N/A		N	2500 TBC	1200 TBC	N/A	N/A	N/A	PCC steel	TBC	N/A	N/A	N/A	X	Refer to Landscape Architect's information for specification of 2.5m high timber SR3 rated security gate and fence NOTE Final location and setting out requires coordination with plant layouts
DG-81	G58	Bin + External Store	NEW	N/A	Double Leaf	N	TBC	TBC	N/A	N/A	N/A	TIMBER	SELF-FINISHED	N/A	N/A	N/A	X	Refer to Landscape Architect Information
DG-82	G58	Bin + External Store	OVERHAUL	N/A	Double Leaf	N	TBC	TBC	N/A	N/A	N/A	PAINT	TBC	N/A	N/A	N/A	X	Gate to be amended by a blacksmith Ironmongery Notes Eurolock with protective cowl Thumbturn to escape lock to be added.

Wrexham Museum Redevelopmen	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01 21/03/2025	JR	JR

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING											DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING / SLIDING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Ground Floor																			
DS-01	N/A	Plant Room Mezzanine	NEW	TYPE 4 SR3 Door	Single	N	1300 TBC ON SITE	810 TBC ON SITE	N/A	N/A	N/A	PCC	TBC	FD30S	N/A	N/A	X	Installation Notes Assumed that the ironmongery is supplied by the door fabricator. Final exit door Hinges/Lock/Levers/Thumb Turn Locks to be suited with other SR3 plant room doors
AH-01	Roof Access Hatch above 1.06	ROOF VOID	NEW	NON-STANDARD TYPE SR3 Roof Hatch	N/A	N	TBC	TBC	N/A	N/A	N/A	PCC	TBC	FD30S	N/A	N/A	X	Installation Notes Assumed that the ironmongery is supplied by the door fabricator. Hinges/Lock/Levers/Thumb Turn Locks to be suited with other SR3 plant room doors

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-01 EXISTING  PROPOSED 	1.01	Football Galleries	OVERHAUL RECLAIMED FROM SITE	TYPE 5 Existing Historic Door + Frame DF 04 relocated	Double Doors fixed shut	N	N/A	N/A	XTG 2051 RECLAIMED 2117	XTG 922/250 RECLAIMED 2X544 (+15) 1085	XTG 42 RECLAIM 45	Stain & Varnish	To match existing	N/A	N/A	N/A	OH-17 TO BE REVIEWED OMIT PUSHPLATES	Repair Notes Remove existing door and frame from opening and make good. Note: Opening to be blocked with 140mm blockwork ising adjustable wall starter Adjust door and from to suit existing opening. Remove vents and make dood boarded panels to match. Remov e modern ironmongery and make good door and frame. Agree scope of works with AABC Existing Ironmongery Pivot Hinge Top+Bottom - remove and make good door and frame, use to repair others Air Vent x2 (remove and make good doors) 1x Door Closer - remove and make good door and frame 2x Lever Handles (both sides of single leaf) - remove and make good doors 2 x cabin hooks and eyes - remove and make good High/Low level bolts on both doors - remove and make good, use to repair others Rebate Lock and latch - remove and make good door leaves RHS Door restricted opening (high pivot falling off) - repair FD Keep shut sign - remove
DF-01 (cont)																		Ironmongery Notes Doors to be fixed shut in frame. 2 x traditional push plates to doors
DF-02  	1.04	Beginnings	OVERHAUL	TYPE 1	Single	Y	N/A	N/A	2232 (1780)	972	44	Paint	TBC	FD30S	N/A	N/A	OH-16 requires means of closing the door when FA releases	Existing Ironmongery 3x100mm Hinges Intumescent/ smoke seals in Frame Overhead Door Closer - remove and make good door leaf and frame 600mm Pull Handle 700mm Push Plate 'FD Keep Shut' Sign - remove and make good Kick Plate (Corridor Side) Ironmongery Notes: Electromagnetic Hold open, release on FA and requires a means of closing the door if the existing closer is removed. Eurolock and escutcheons New Welsh/ English fire signage



Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-05	1.04	Beginnings	NEW	TYPE 3C	Single	N	2130 (XTG -TBC on Site)	1200 (XTG - TBC on Site)	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-14	Installation Notes Check existing structural opening size, adjust frame to suit door leaf if required. Setting out of door opening to be coordinated with exhibition layout. Frame to be installed into the reveal to minimise the extent of the swing into 1.04. Ironmongery Notes Needs hold open release on FA during hours of operation, L ockable overnight.
DF-06 	1.37	Stair 3	OVERHAUL	TYPE 1 Existing historic door to be retained	DOUBLE	Y	N/A	N/A	XTG 2150	XTG 590 x 2	XTG TBC	Existing - Conservation clean only	N/A	N/A	N/A	N/A	OH-18 TO BE REVIEWED	Repair Notes HISTORIC STAINED GLASS DOORS AND PARTITION. Allow for conservation of clean of doors, secreen and glazing. Existing Ironmongery Pivot hinge Top/bottom - overhaul High/low level bolts - provide floor receivers for open and closed positions (Brass sections of pipe for open and closed position. Other ironmongery - push/ pull plares to be cleaned and re-fixed. Ironmongery Notes WCBC to confirm if lock required.
DF-07 	1.02	Lobby	OVERHAUL	TYPE 1 Existing door	Single	N	N/A	N/A	2025	926	42	Paint	TBC	FD30S	N/A	N/A	ND-14/A Incorrect - door retained Requires means of closing the door when FA releases	Fire Remedial Works The fire stopping between the fire door lining and structural opening is recommended to be fully raked out and removed and replaced with an approved fire stopping solution for the intended field of application to comply with FD30S. Existing Ironmongery 3x100mm Hinges Intumescent/ smoke seals in Frame Overhead Door Closer 600mm Pull Handle 700mm Push Plate 'FD Keep Shut' Sign - remove and make good Kick Plate (Corridor Side) Ironmongery Notes: Electromagnetic Hold open, release on FA and requires a means of closing the door if the existing closer is removed. Eurolock/ escutcheons required. New Welsh/ English fire signage

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-09 	1.06.	Wrexham Galleries Introduction	OVERHAUL	TYPE 1 Existing historic door to be retained and fixed shut	Single	N	2100	775 (TBC On Site)	2000	605	47	Oak Varnish	Clear Matt	N/A	N/A	N/A	X	Repair Notes Door Fixed Shut - Lock door and hand over keys to WCBC for safe keeping. Enusre door is operational for future proofing/ reversibility. Existing Ironmongery Brass Knob both sides of door - retain Rim lock and receiver - retain 2x 130mm(h) hinges - retain Escutcheon - retain 1x High level bolt lock?(digi?) - remove and make good
DF-13 EXISTING  PROPOSED 	1.33	SE Turret	OVERHAUL FIX HISTORIC DOOR RECLAIMED FROM SITE	TYPE 1 Fix historic door reclaimed from site DG-19	Single	N	N/A	N/A	XTG 1842 RECLAIMED 1917	XTG 628 RECLAIMED 712	XTG 42 RECLAIM 62	Paint	TBC	N/A	N/A	N/A	OH-19 TO BE REVIEWED	Repair Notes Exhibition design requires a lockable dummy door (Key suiting TBC). Remove bund and make good existing frame and architrave to match. Make good door leaf and frame where ironmongery removed or amended. Scope of work to be agreed with AABC. Existing Ironmongery 3 x 100mm hinges - remove and make good door and DG-19 frame 1no. pull handle - remove and make good 1no. padlock bolt (175mm) - remove and make good 1no. back plate - remove and make good DG-19 Ironmongery Notes 2 x hinges (possibly T) Suffolk latch and reciover Eurolock nightlach adnd receiver
DF-18A	1.18	Changing Places	NEW	TYPE 3C	Single	N	2100	1135	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-15 TO BE REVIEWED	Installation notes RADAR LOCK AND KEYS CONFIRMED BY WCBC 1000mm clear opening to be achieved Ironmogery Notes Eurolock required - additional security for window Restrictor/ door stop advisable?



Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330.4331.4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-20 	1.34	SW Turret	OVERHAUL	TYPE 1 Existing historic door to be retained	Single	N	N/A	N/A	1828	622	46	Paint	TBC	N/A	N/A	N/A	OH-08	Repair Notes Remove existing night latch? Make good door and frame Existing Ironmongery 2x 85mm (h) T-hinges Suffolk Latch and receiver - repair/ adjust and make operable Ironmongery Notes Eurolock/ night latch and reciver installed (Suiting TBC)
DF-21  	1.19	Office 3	NEW	TYPE 3A	Single	N	N/A	N/A	2010	767	51	Paint	TBC	FD30	N/A	N/A	OH-10 INCORRECT NEW FIRE DOOR	Installation Notes New door and frame to site dimensions Ironmongery Notes Hinges O/head closer Push/pull plates Eurolock/ Escutcheons - WCBC TBC
DF-22  	1.21	Office 2	OVERHAUL	TYPE 1 Existing historic door to be retained	Single	N	N/A	N/A	1994	778	36	Paint	TBC	N/A	N/A	N/A	OH-20	Repair Notes Remove redundant ironmongery and make good door and frame. Overhaul existing ironmongery and ensure operable. Existing Ironmongery 2x100mm (h) hinges - retain Night latch and reciever - remove and make good door and frame Rimlock and latch set - retain/ adjust Coathook - painted - retain 2 x Door Knobs - retain/ adjust Ironmongery Notes Eurolock/ night latch Traditional flat brass escutcheon - replace missing to match