

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-23 EXISTING  PROPOSED 	1.22	Football Galleries Introduction	OVERHAUL FIX HISTORIC DOOR RECLAIMED FROM SITE	TYPE 5 Fix historic door + frame reclaimed from site into opening (DF-24 from 1.22/1.01)	Single	N	N/A	N/A	XTG 1974 RECLAIMED 1991	XTG 760 RECLAIMED 760	XTG 34 RECLAIM 50	Paint	TBC	N/A	N/A	N/A	X	Repair Notes Repair DF-24 door and frame and fit in this location, modify to suit. Fix door in frame Existing ironmongery Remove all - make good door and frame Remove ironmongery for use elsewhere NOTE: WALL TYPE PROVIDES FR60 BUILD UP THRESHOLD, MOVE DOOR AND FRAME.
DF-26A	1.35	Stair 1	NEW	TYPE 3A	Single	Y	N/A (SITE DIM TBC)	N/A (SITE DIM TBC)	1992	827	43	Paint	TBC	FD30S	N/A	SH	ND-27	New Ironmongery Make Lockable
DF-27  	1.28	WC	OVERHAUL	TYPE 1 Existing historic door to be retained	Single	N	N/A	N/A	2047	680	47	Paint	TBC	N/A	N/A	N/A	X	Repair Notes Retain existing door frame and ironmongery. Make good door and frame Existing Ironmongery 2x140mm(h) hinges 2x Door Knobs Escutcheon Rim lock and latch and reciver Bolt and reciver Historic Toilet Roll holder


Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-28 	1.27	WC Lobby	OVERHAUL	TYPE 1 Existing historic door to be retained	Single	N	N/A	N/A	2050	826	46	Paint	TBC	N/A	N/A	N/A	OH-10 TO BE REVIEWED	Repair Notes Retain existing door frame and ironmongery. Make good door and frame Existing Ironmongery 2x 130mm (h) hinges Escutcheon 2x Door Knobs Rim lock and latch Ironmongery Notes Provide new signage ROOM NOT IN USE - KEEP LOCKED
DF-30  	1.29	Collection Store	OVERHAUL	TYPE 1 Retain existing door	Leaf and Half	N	N/A	N/A	2050	470	50/20	Paint TBC	TBC	FD30S/ FD180/240	N/A	N/A	ED-01 TO BE REVIEWED	The original specification for this door identifies it as 3-4 hour fire resistance to protect the collection sotre. Fire Remedial Works Remove services passing through mastic. Rake out mastic and provide fore stopping to provide 240FR to match the door. Note: Fire stopping remedial works required between the frame and aperture which is tested for a steel door application as the steel will expand at different rates to timber fire door assemblies. Ironmongery Notes New eurolock cylinder (Suiting TBC) New Welsh/ English fire signage to match size of existing
DF-31 	1.30.	Comidor	OVERHAUL	TYPE 1 Retain existing Door	Single	Y	N/A	N/A	2040	825	43	Paint	TBC	FD30S	N/A	N/A	OH-21 TO BE REVIEWED	Fire Remedial Works Replace the existing hinges with 3no. UKCA/CE embossed Certifire hinges. Existing Ironmongery 3 x hinges - remove and replace - see FE notes 1 x o/head closer 2 x foot plates 1 x pushplate 1 x pull handle 1 x eurolock with thumbturn and escutcheons - remove and make good 2 x 'FDKS signs' - remove and make good 3 x directional signs - remove and make good Ironmongery Notes New eurolock, thrmbturn/ handle and escutcheons New Welsh/ English fire signage Replace hinges

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-32 	1.32	Collection Workshop	OVERHAUL	TYPE 1 Retain existing Door	Single	Y	N/A	N/A	2038	820	42	Paint	TBC	FD30S	N/A	N/A	OH-22 TO BE REVIEWED	Fire upgrades All tolerances between the leaf and frame should be verified prior to formal handover. Adjust door leaf to ensure. Existing Ironmongery 3 x hinges 1 x o/head closer - confirm operational 2 x foot plates 1 x pushplate 1 x pull handle 1 x eurolock with thumbturn (?) and escutcheons 2 x 'FDKS signs' - remove and make good 3 x directional signs - remove and make good - WCBC to confirm Ironmongery Notes New eurolock cylinder (Suiting TBC) New Welsh/ English fire signage Digilock
DF-33  	1.31	Collections Office	OVERHAUL	TYPE 1 Retain existing Door	Single	N	N/A	N/A	2050	840 (-20) XTG STEEL DOOR	70 (50+20)	Paint TBC	TBC	FD30S	N/A	N/A	ED-01 TO BE REVIEWED	The original specification for this door identifies it as 3-4 hour fire resistance to protect the collection sotre. Remedial works Remove services passing through mastic. Rake out mastic and provide fore stopping to provide 240FR to match the door. Note: Fire stopping remedial works required between the frame and aperture which is tested for a steel door application as the steel will expand at different rates to timber fire door assemblies. Ironmongery Notes New eurolock cylinder (Suiting TBC) New Welsh/ English fire signage to match size of existing
DF-34  	1.29	Collection Store	OVERHAUL	TYPE 1 Retain existing Door	Single	Y	N/A	N/A	2047	825	43	Paint	TBC	FD30S	N/A	N/A	ED-01 TO BE REVIEWED	No works proposed to door + frame Existing Ironmongery to be amended 2 x 'FDKS' - r4emove and make good 1 x Eurlock cylinder Ironmongery Notes New eurolock (Suiting TBC) New Welsh/ English fire signage

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-35	1.09	Lobby	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-16	Notes 926mm min door leaf Linked to fire and security alarms
DF-36	1.41	Conflict & Struggle	NEW	TYPE 3A	Single	Y	2100	1255	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-17	Hold open to release on fire alarm (As DF-05), lockable overnight 1170mm door leaf to be achieved
DF-37	1.07	Landing	NEW	TYPE 2A	Single	N/A	2400 (TBC On Site)	1275 (TBC On Site)	N/A	N/A	N/A	Glazed PCC Aluminium	TBC	FD30	Rw30dB	SH	X	Ironmongery by fabricator Automatic door on wall mounted push pads both sides, release on fire alarm Lockable
DF-38	1.14	Wheelchair Accesible WC	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-19 vs ND-09 TO BE REVIEWED	Lockable 926mm door leaf required
DF-39	1.15	Family Room	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-20 vs ND-10 TO BE REVIEWED	Lockable 926mm door leaf required
DF-40	1.39	Gender Neutral WC	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	N/A	Rw30dB	N/A	ND-06	No deadlock

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-41	1.40.	Cleaners Store	NEW	TYPE 3C	Single	N	2100	900	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-07	Provide Digilock No deadlock
DF-42	1.16	Corridor	NEW	TYPE 3B	Leaf and Half	Y	2100	1575 TBC	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-21 TO BE REVIEWED VS ND-08 AS DF-76	ACCESS CONTROL NEEDS TO BE INCLUDED TO RELEASE AS FIRE ALARM SOUNDS (WCBC identify no lock, but access control - provide ironmongery options) DG-76 had ND-08 ironmongery DF-42 hasND-21 ironmongery both need access control adding and amendment
DF-43	1.16	Office	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	Paint	TBC	FD30S	Rw30dB	N/A	ND-22 TO BE REVIEWED	Deadlock TBC Digilock/electronic access (TBC)
DF-44	1.07	Landing	NEW	TYPE 2A	Single	N/A	2400 (TBC On Site)	1275 (TBC On Site)	N/A	N/A	N/A	Glazed PCC Aluminium	TBC	FD30	Rw30dB	SH	X	Fabricator to provide Ironmongery Autodoors on PIR in 1.07 and pushpad in 1.22, to release on FA Lockable
DF-45	1.01	Football Gallery	NEW	TYPE 3C	Single	N	2100 (TBC On Site)	900 (TBC On Site)	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N	X IRONMONGERY NOW REQUIRED	Existing Architraves to be overhauled As DF-35? Lockable, push pad to open Door to be linked to security/ fire alarm

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-46	1.24	Museum AV Room	NEW	TYPE 3C	Single	N	2100	1010	N/A	N/A	N/A	Paint	TBC	FD30S	N/A	N/A	ND-13 TO BE REVIEWED	ACCESS CONTROL AND NO LOCK REQUESTED BY WCBC 926mm door leaf Provide Digilock
DF-48 	1.05	Trade & Industry	OVERHAUL	TYPE 4 Existing Historic doors retained	Double Leaf	N	XTG (TBC on site) 2130	XTG (TBC On Site) 1192	2117	550 X 2	45	Existing timber door with stain and varnish finish	TBC	N/A	N/A	N/A	OH-23	Repair Notes Turn door + frame to open into 1.05. Remove grilles and make good. Retain hinges if required Add bolts + recievers for open and shut postions, traditional ironmongery. Review scope of repairs with AABC prior to undertaking. Existing Ironmongery 2 x Pivot Hinges Top+Bottom - overhaul 2 x Air Vent - Remove and make good door leaves 2 x Overhead Door Closers - Remove and make good doors and frame 2 x Cabin hooks and stays -remove and make good doors and frame 13mm Rebate Rebate Lock and Latch (+reciever - modern) - remove and make good doors 2 Handle Levers - remove and make good doors High/Low level bolts (in need of new bolt recievers) *Need foot recievers in open/closed positions Ironmongery Notes 2 x traditional pull handles 2 x traditional push plates, size to match original 2 x traditional floor bolts and recivers for open and closed positions
DF-49	1.16	CORRIDOR	NEW	TYPE 3A	Single	Y	2100? TBC - CHECK	1255	N/A	1170 required	N/A	Paint	TBC	FD30S	N	N/A	ND-32	Hold-open to release on FA, lockable.
DF-50-A NOTE DOOR LOCATION MOVED	1.01	FOOTBALL GALLERY	NEW	TYPE 3C	N/A	N	N/A	N/A	TBC ON SITE	TBC ON SITE	TBC ON SITE	Paint	TBC	FD30	N	N/A	X	Repair Notes Remove existing modern door and retain frame and make good. Install new door and frame within door reveal (Behind current location) New door to be fixed shut in frame ALLOW FOR RENEWING PLASTERBOARD FINISH TO 1.06 SIDE IF REQUIRED

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB
C01		

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

Text in Green/ Highlights in ???- good to go!!

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUMROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
First Floor																		
DF-51 (Existing DF-19)	1.19	OFFICE 3	NEW	TYPE 3A	Single	Y	N/A	N/A	1989	807	39	Paint	TBC	FD30	N	N/A	OH-10 TO BE REVIEWED NEW FIRE DOOR	Installation Notes New door and frame in existing opening. Ironmongery Notes Hinges O/head closer Push/pull plates Eurolock/ Escutcheons - WCBC TBC

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Second Floor																		
DS-02	2.02	Plant Room Mezzanine Location TBC	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw52dB TBC	N/A	ND-33 TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage
DS-03	2.02	Plant Room Mezzanine Location TBC	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw52dB TBC	N/A	ND-33 TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage
DS-04 PROVISIONAL	TBC	Roof Void	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw30dB	N/A	ND-33P TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage
DS-05 PROVISIONAL	TBC	Roof Void	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw30dB	N/A	ND-33P TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600 , 241084-PUR-00-01-DR-A-2610 , 241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510 , 241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520 , 241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Second Floor																		
DS-06 PROVISIONAL	TBC	Roof Void	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw30dB	N/A	ND-33P TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage
DS-07 PROVISIONAL	TBC	Roof Void	NEW	TYPE 3C	Single	N	2100 TBC ON SITE	1010 TBC ON SITE	N/A	N/A	N/A	PAINT		FD30S	Rw30dB	N/A	ND-33P TO BE REVIEWED	Ironmongery Required. Hinges Latch Lever Closer Signage

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Internal Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Openings																		
OPG-01	G11/G12	Special Exhibition Gallery / Activities / Special Exhibition Gallery	NEW	N/A	N/A	N/A	2100	2435	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SH SG-07	X	SR4 Shutter
OPG-02	G01/G02	Welcome / Retail	NEW	N/A	N/A	N/A	XTG	XTG	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SH SG-03	X	SR1 Concertina Shutter
OPG-03	G24/G25	Learning and Community Hub 1 / 2	NEW	N/A	N/A	N/A	2310	3600	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	Movawall partition to fabricator's details
OPF-01	1.05/1.41	Trade and Industry / Conflict & Struggle	NEW	N/A	N/A	N/A	2400	3500	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	

Wrexham Museum Redevelopment	Schedule	Author
241084-PUR-00-XX-SH-A-0005	Internal Door Schedule	

Version	Drawn	Checked
P01 06/10/2023	CH	PS
P02 17/10/2023	CH	PS
P03 14/12/2023	CH	PS
P04 19/01/2024	PS	PS
P05 22/08/2024	CH	ZB
P06 13/09/2024	CH	JR
P07 28/10/2024	CH	ZB

Notes:
This Schedule should be read in conjunction with the following drawings:
Wall Type Drawings: **241084-PUR-00-GF-DR-A-2600** , **241084-PUR-00-01-DR-A-2610** , **241084-PUR-00-02-DR-A-2615** & **241084-PUR-00-RF-DR-A-2620**
Fire Strategy Drawings: **241084-PUR-00-GF-DR-A-2510** , **241084-PUR-00-01-DR-A-2511** & **241084-PUR-00-02-DR-A-2512**
Security Strategy Drawings: **241084-PUR-00-GF-DR-A-2520** , **241084-PUR-00-01-DR-A-2521** & **241084-PUR-00-02-DR-A-2522**

IRONMONGERY PROPOSALS IN ABEYANCE - TBC

LOCATION				OPENING										DOOR PERFORMANCE				
DOOR REF NUMBER	ROOM NUMBER	ROOM NAME	NEW / OVERHAUL / RECLAIMED FROM SITE	NEW DOOR TYPE TYPE 1 - EXISTING DOORS TYPE 2A/B - ALUPROF GLAZED DOORS TYPE 3A/3B/3C - NEW DOORS TYPE 4 - SR RATED TYPE 5 - HISTORIC DOOR RELOCATED REFER TO DRAWINGS 4330,4331,4332 FOR DOOR TYPES	SINGLE / DOUBLE LEAF / LEAF AND HALF / DOUBLE SWING	VISION PANEL	NEW SO HEIGHT (mm)	NEW SO WIDTH (mm)	EXISTING DOOR LEAF HEIGHT (mm)	EXISTING DOOR LEAF WIDTH (mm)	EXISTING DOOR LEAF THICKNESS (mm)	DOOR FINISH	COLOUR	FIRE RATING	ACOUSTIC RATING	SHUTTERS	IRONMONGERY (ALLGOOD SET NUMBER)	COMMENTS
Openings																		
OPF-02	1.10/1.11	Communities / Daily Life	NEW	N/A	N/A	N/A	2400	1500	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	
OPF-03	1.01/1.22	Football Galleries / Football Galleries Intorduction	NEW	N/A	N/A	N/A	1530 TBC ON SITE	1485/ 2689 TBC ON SITE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	Refer to drawing 4505
OPF-04	1.01/1.22	Football Galleries / Football Galleries Intorduction	NEW	N/A	N/A	N/A	1580 TBC ON SITE	1485/ 2689 TBC ON SITE	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	Refer to drawing 4506
OPF-05	1.07/1.16	Landing / Corridor	NEW	N/A	N/A	N/A		1050	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	X	
OPF-06	1.09/1.36	Lobby/ Stair 2	EXISTING	N/A	N/A	N/A	XTG	XTG	N/A	N/A	N/A	N/A	N/A	N/A	N/A	SH	X	SR4 Shutter