

This information is confidential and the copyright property of CWLS Ltd. It is released on the condition that none of the information shall be disclosed or reproduced in whole or part to/by any third party without prior written consent from CWLS Ltd. Subject to Terms & Conditions a copy of which is available upon request.

Survey Control Markers have been established for Topographic Mapping purposes only and should not be used for Construction or Setting-Out without written approval from CWLS Ltd

Legend

- RS

Road Sign
- GR

Road Gully
- LP

Lighting Column or Post
- EP

Electric Transmission Pole
- GP

Gate Post
- Gate

Gate
- Tree/Large Shrub

Tree/Large Shrub
- 5

PGM / Site Control Station
- MH

Manhole Cover Circular
- MH

Manhole Cover Rectangular
- Kerb Channel Line

Kerb Channel Line
- Kerb Top/Back

Kerb Top/Back
- Verge

Verge
- Fence/Line

Fence/Line

Station	Easting	Northing	Level
1	332157.252	352364.969	91.145
2	332145.818	352375.469	92.508
3	332109.614	352388.312	94.094
4	332106.210	352412.092	93.906
5	332102.207	352455.922	93.571
6	332098.169	352499.726	93.178
7	332095.771	352539.062	92.890

BURIED ASSETS DETECTED ON SITE:				
LINETYPE		SERVICE DESCRIPTION		
BT	BT	TELECOMMUNICATIONS (BT)		
CATV	CATV	TELECOMMUNICATIONS (CATV)		
TELE	TELE	TELECOMMUNICATIONS (OTHER)		
G	G	GAS		
TCSU	TCSU	TRAFFIC CONTROL SENSOR UNIT		
SL	SL	STREET LIGHTING		
LV	LV	LOW VOLTAGE		
HV	HV	HIGH VOLTAGE		
W	W	WATER		
FWD	FWD	FOUL WATER DRAINAGE		
SWD	SWD	SURFACE WATER DRAINAGE		
FWRM	FWRM	FOUL WATER RISING MAIN		
CS	CS	COMBINED SEWER		
OF	OF	OIL/FUEL		
U(GPR)	U(GPR)	UNKNOWN UTILITY (GPR)		
U(EML)	U(EML)	UNKNOWN UTILITY (RADIO)		
EOT		A/R	ASSUMED ROUTE	
01	07/12/21	CW	TB	CW
Issue	Date	By	Chkd	Appd

Carl Williams Land Surveys Ltd
The Studio
15 Millfield
Neston
CH64 3TF
info@cwlandsurveys.com
www.cwlandsurveys.com

Client
Castle Green Homes

Job Title
Land off Mold Road
Gwersyllt

Drawing Title
Topographic & GPR
Utility Surveys


Scale at A1
1:500

Plot ID

Drawing Status

For Information

Job No B444-00	Drawing No Figure 01	Issue 01
--------------------------	--------------------------------	--------------------



Quality Level of Utility Survey Outputs:

The drawing has been derived from the amalgamation of several data sets: utility service provider buried asset plans, visual confirmation by way of lifting manholes, and measuring depth, type and location of services, electromagnetic detection, and GPR scans.

All the data sets have been allocated a "weighting" based upon the likely accuracy and confidence. The final amalgamation is performed by polynomial rubber sheet distortion of service provider assets plans for a "best fit" to resemble on-site survey data findings as close as possible

The accuracy of the horizontal location of each utility is defined by Table 1 'Quality level of survey outputs PAS128(normative)' for QL-B2P = +/-0.25m or +/-40% of detected depth whichever is greater.

The accuracy of the vertical location of each utility as defined by Table 1 'Quality level of survey outputs PAS128(normative)' for QL-B2P = +/-40% of detected depth.

Care should be taken by designers when utilising the findings within this drawing, and should confirm depths by visual confirmation/verification using vacuum excavation or slit trench technology if a higher degree of accuracy is required to meet the design brief specification.

Utility Survey Disclaimer:

We have endeavored to locate as many buried services as possible using the Best Available Technology (BAT) and applying the Best available Techniques as defined under guidance from the The Survey Association (TSA) and the British Standard PAS128 for Utility Surveys.

However, the user of this drawing should be aware that the results found using Best Available Technology are subject to errors and tolerances resulting from geophysical properties of the subsurface (which can be a significant limitation/inhibitor to the survey) , out of the control of the operator, being surveyed/scanned. In addition survey findings are interpreted on site in real-time and thus are subject to interpretative and subjective variations. This information is given without warranty, the accuracy thereof cannot be guaranteed.

The accuracy of the findings indicated within this drawing, cannot be guaranteed or indemnified, and should only be used as a guide as defined by the Health & Safety Executives (HSE) guideline - HSG47.

Lines on this drawing indicating the presence of buried services may actually be indicating the presence of closely bundled cables or pipelines, therefore the user of this drawing should not assume that a single line is indicative of the number of services within the area. In addition services below detected utilities may be masked from detection by the shadow cast from shallower depth services.

Metal pipes, communication cables and earth bonds can 'present' electromagnetic fields similar to that of high voltage and low voltage cables under load, if alternating electromagnetic fields are in close proximity from other power cables or sub-stations etc.

The designation of the services (i.e. is the detected service a water pipe or as pipe?) is open to interpretation and is based upon a number of references such as visible surface features (water stop valves, or gas meter) and utility provider records (indicating whether high voltage or low voltage). The best technology deployed is limited in its ability to define the exact type of service. The user of this drawing should prove, by means of safe-excavation, the type of service if critical to the design.

Equipment Deployed:

IDS Dual Frequency Ground Penetrating Radar (GPR) with on-site operator interpretation.

Radiodetection RD8000 & T10 Electromagnetic Generator and Precision Cable Locator.