Planting Schedule (Individual)

Climber

Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
3	Hh Gold	Hedera helix 'Goldheart'	80-100cm			C	5L	Several shoots		

Hedge

Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/Lin. m
57	Fs hed	Fagus sylvatica - hedge	100-125cm		1/2	C	10L		Transplant (seed-raised)	3.00
369	PRR	Photinia x fraserii 'Red Robin'	100-125cm		3x	C	10L			3.00

Herbaceous

Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
35	Acnths ml	Acanthus mollis	30-40cm			C	3L			5.00
105	CmlD	Carex morrowii 'Ice Dance'	25-30cm			C	3L			5.00
94	Cx mE	Carex morrowii 'Evergold'	30-40cm			C	3L			5.00
50	LmLB	Liriope muscari 'Lilac Beauty'	30-40cm			C	3L			5.00

Shrub

Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
12	Acb jR	Aucuba japonica 'Rozannie'	30-40cm			C	3L			4.00
45	BcgS	Brachyglottis 'Sunshine'	40-60cm			C	3L	Branched		4.00
57	BrbTG	Berberis thunbergii 'Tiny Gold'	30-40cm		2x	C				4.00
8	CA	Cordyline australis 'Sundance'	80-100cm		0/1	B	10-15L			
78	CcFC	Caryopteris x clandonensis 'First Choice'	30-40cm		1/1	C	3L			4.00
78	Cnth B	Ceanothus 'Burkwoodii'	40-60cm			C	3L			4.00
89	Ct	Choisya ternata	40-60cm			C	3L	Bushy		3.00
8	CtS	Choisya ternata 'Sundance'	60-80cm			C	10-15L	Bushy		
77	EfEG	Euonymus fortunei 'Emerald 'n' Gold'	30-40cm			C	3L	Bushy		4.00
89	EjWS	Euonymus japonicus 'White Spire'	30-40cm		1/1	C	3L			4.00
49	FMP	Fuchsia 'Mrs Popple'	30-40cm			C	3L	Bushy		4.00
63	Hb AG	Hebe 'Autumn Glory'	30-40cm			C	3L			4.00
108	Hb GG	Hebe 'Green Globe'	30-40cm			C	3L			4.00
87	HmBW	Hydrangea macrophylla 'Blue Wave'	30-40cm			C	3L			3.00
5	HpL	Hydrangea panicula 'Limelight'	60-80cm			C	10-15L			
80	HWG	Hebe 'White Gem'	30-40cm			C	3L	Bushy		4.00
48	MaA	Mahonia aquifolium 'Apollo'	40-50cm			C	3L	Several shoots		4.00
6	Mhn rp	Mahonia repens	30-40cm		2x	C	3L			
1	MmWS	Mahonia media 'Winter Sun'	80-100cm			C	15L	Bushy		
6	PBE	Philadelphus 'Belle Etoile'	40-60cm			C	10-15L	Branched		
32	PfAb	Potentilla fruticosa 'Abbotswood'	30-40cm(D)			C	5L	Bushy		4.00
60	PjLH	Pieris japonica 'Little Heath'	20-25cm			C	5L	Bushy		4.00
4	PMS	Phormium 'Maori Sunrise'	60-90cm		0/1	C	10L			
15	PRR	Photinia x fraserii 'Red Robin'	80-100cm		3x	C	10-15L			
66	Ptt tn TT	Pittosporum tenuifolium 'Tom Thumb'	30-40cm			B				3.00
3	RMM	Rhododendron 'Madame Masson'	40-60cm			C	15L	Branched		
64	Sh	Sarcococca humilis	25-30cm			C	3L			4.00
31	SjF	Spiraea japonica 'Firelight'	30-40cm			C	3L	Bushy		4.00
79	SjG	Spiraea japonica 'Goldflame'	30-40cm			C	3L	Bushy		4.00
61	SjR	Skimmia japonica 'Rubella'	30-40cm			C	3L	Bushy		4.00
75	Sk KG	Skimmia confusa 'Kew Green'	30-40cm			C	3L	Bushy		4.00
44	Src hk	Sarcococca hookerana digyna	30-40cm		1/1	C	3L			4.00
67	VcmA	Vinca minor 'Alba'				C	3L			4.00
115	Vd	Viburnum davidii	30-40cm			C	3L	Bushy		4.00
75	Vt	Viburnum tinus	30-40cm			C	3L	Bushy		3.00

Tree

Nr	Code	Plant Name	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Density/m2
3	AaRH	Amelanchier arborea 'Robin Hill'	300-350cm	10-12cm	2x	RB			Selected Standard	
3	AC	Amelanchier canadensis	300-350cm	10-12cm	2x	RB			Selected Standard	
3	Acr cm	Acer campestre	400-450cm	14-16cm	3x	RB			Standard (extra-heavy)	
6	Al (M-S)	Amelanchier lamarckii (multi-stem)	300-350cm		3x	C	35-50L		Multi-stem	
11	Bp	Betula pendula	400-450cm	14-16cm	3x	RB			Standard (extra-heavy)	
2	Fs	Fagus sylvatica	400-450cm	14-16cm	3x	RB			Standard (extra-heavy)	
4	PA	Prunus 'Amanogawa'	300-350cm	10-12cm	2x	RB			Standard (Selected)	
2	PcC	Pyrus calleryana 'Chanticleer'	300-350cm	14-16cm	3x	RB			Standard (Extra heavy)	

Planting Schedule

Hedge Mix

Nr	Code	Plant Name	Mix%	Height/Spread/Grade	Girth	Age	Root	Container	Habit	Form	Lin. mt
61	Cb - h	Carpinus betulus	50.00%	100-125cm			C	10L			3.00
61	Il aq - h	Ilex aquifolium	50.00%	100-125cm			C	10L			3.00

NOTES ON PLANTING

1 Topsoil: Topsoil shall be spread to min 450mm depth over planting beds and 150mm depth over turf areas and graded to fall. Topsoil should be in accordance with BS3882:2015 and where subsoil is required, to be in line with BS8601:2013.

2 Herbicide and Cultivation: Topsoil to be treated with an application of herbicide prior to planting, where necessary, strictly in accordance with the Control of Pesticides Regulations1986 (or otherwise updated/ superceded legislation), and following manufacturer's instructions by qualified staff. The topsoil shall then be cultivated to 150mm depth.

3 Container Grown Shrubs, Transplants and Whips: Shrubs and transplants shall comply with the National Plant Specification. Shrubs shall be planted in pits 300 x 300 x 200mm depth, and the backfill shall include 3 litres Peat Free Tree and Shrub Compost. Specimen plants to be planted in a pit 400 x 400 x250mm depth with 5 litres Tree and Shrub Compost. BR whips should be notch planted as required and healed into position. All whips to be protected by a spiral bound shrub guard secured into place with a timber stake. Hedgerow planting to be planted in a double staggered row at 450mm centres.

4 Herbicide: Spot treat with herbicide throughout the maintenance period in accordance with the manufacturer's instructions.

5 Bark Mulch: All Ornamental Planting beds to receive 75mm depth pulverised ornamental bark mulch.

6 Position of Plants: Final position of trees and shrubs subject to confirmation of service location and approval of statutory undertakers.

7 TREES - TREES - MULTISTEM, SELECTED STANDARD, HEAVY STANDARD**:** Tree pit to be 600x600x600mm depth. Pit backfilled with 1 parts topsoil to BS3882-2015, 2 parts tree planting compost to depth of 500mm, loosen and shape base to be to depth of 100mm fill with clean stone. If within lawn tree to be set in circle area of bark mulch 75mm depth at 500mm diameter.
Tree to be secured with 1nr stake, to be 65mm diameter treated softwood driven firmly into the ground. Stake to be pointed at one end. Stake fix to tree with adjustable soft tree tie with spacer. Rubber tree strap secured with 1No nail (galvanised round head).

EXTRA HEAVY STANDARD**:** Tree pit 900x900x900mm depth with 150mm depth of clean stone to the base, 300mm depth good quality topsoil to BS3882-2015 and 450mm subsoil to BS8601:2013. If planted within lawn tree to be set in circle area of bark mulch 75mm depth at 500mm diameter. Double stakes to be 1000mm above ground and fixed to tree with suitable rubber tree ties (with the tree in the middle). Trees to be planted with an irrigation pipe (to wrap around the rootball of the tree) and secure the end of the pipe to the tree stake.
8 Watering: Plant only into moist soil and water thoroughly to the full depth of soil immediately after planting. Water regularly through the establishment period (minimum 3 months) to prevent dehydration. The trees should be watered through the irrigation pipe to ensure that the water gets down to the rootball. These trees should be watered regularly throughout spring-summer during the first 2 years to ensure that the tree root system establish well.

9 Wildflower Meadow for Wetlands:
Timing - Sow meadow during March and April or in September. When sowing into heavy soils, sow in March/April to avoid seeds/seedlings rotting in waterlogged soils.
Ground Preparation -

- Control or remove weeds before sowing. For small areas, remove weeds by hand. For larger areas, a weed suppressing membrane or black plastic can be laid over the area 3 months prior to sowing to prevent weed growth. For larger areas and where vigorous perennial weeds, such as nettles, docks and dandelions, are present in large number, non-chemical control methods may not be effective. In these situations instead spray off existing vegetation using non-residual systemic glyphosate-containing weedkillers
- Rotavate soil and rake to make even seed bed

Sowing -

- Wildflower meadow to be sown at 4g per m
- Mix wildflower seed with silver sand to aid even seed distribution and to show area that have been covered. Sow half lengthways and half widthways for even coverage.
- Rake in seeds lightly

10 Grass Seeding: Sow late summer to mid autumn. Prepare ground by removing any existing vegetation, large stones and roughly levelling. Grass seed should be spread at 50g per m … After sowing, lightly rake over area and water.

11 Turf: Complete ground preparations before turf is delivered to site to avoid turf drying out. Turf should be laid immediately on delivery. Remove all existing vegetation from area to be turfed and spread 150mm depth of top soil. Dig over or rotavate soil before laying turf if soil is compacted. Rake, lightly compact, and water soil. Stagger the joins when laying the turf. Water turf after laying and every day for the next 2-3 days, especially in periods of low rainfall.

12 Soil compaction is likely to have occurred during construction on site. A site inspection should be carried out by a landscape professional to assess the level of soil compaction, including drainage testing to see if the ground is likely to become waterlogged. If the ground is deemed to be too compacted for plant growth and to drain adequately then remediation works should be carried out. This could include rotavation of the soil using a push along rotavator and/or ground being broken up with spades or small machinery. A second site inspection should then take place to ensure that the soil is fit for purpose.

13 Tree species selected subject to soil conditions and NHBC guidance. Root barriers may be required subject to findings from soil analysis and engineer's details.

GENERAL NOTES

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.

2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

REVISION NOTES

Rev	By	Description	Date
E	RN	Amended as per client comments: Replaced Pyrus hedge with hedge mix; addition of Medium size trees.	01.07.25
D	AJ	Updated in line with the 9plots latest layout	28.05.25
C	TS	Updated in line with the 9plots latest layout	08.01.25
B	MC	North-eastern part revised to integrate with the adjacent site	26.04.24
A	JW	Revised in line with latest layout P03	15.02.24

Client
SG ESTATES

Project
Royal British Legion, Llay

Description
Planting Plan (2 of 2)

Status
For Approval

Scale @ A3	Drawn	Checked	Date
-	TS	CT	15.04.21

Job number	Drawing number	Revision
3790	202	E

N

tpm landscape
chartered landscape architects
address: 4th Floor Studio 10 Little Lever St Manchester M1 1HR
tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk