

Notes

Hardstanding 6.0m x 3.0m plus gravel to sides
Dropped Kerb Required - tie in to dropped kerb at No.56

It is prohibited to remove hedges during the nesting season between 01st March and 31st August

Check for Virgin Media cables in footway and garden areas

KEY

- Precast Concrete BN Kerb 125 x 150mm
- Precast Concrete DL1/DR1 Kerb
- Precast Concrete EBN Kerb

HARDSTANDING SPECIFICATION

Surface Course, Dense Bitumen Macadam,
10mm nominal size,depth 40mm
Binder Course, Dense Bitumen Macadam,
20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 300mm

FOOTWAY SPECIFICATION

Surface Course, Dense Bitumen Macadam,
10mm nominal size,depth 20mm
Binder Course, Dense Bitumen Macadam,
20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 150mm

All setting out to be agreed with WCBC
prior to commencing works on site

WREXHAM COUNTY BOROUGH COUNCIL
Housing Services,
Housing and Public Protection Department,
Ruthin Road,
Wrexham.
LL13 7TU
Tel: (01978) 315300 Fax: (01978) 315355

Project: 54 Cae Gwilym Lane			
Detail: Proposed Hardstanding and dropped kerb			
Drawn By: AJ	Date: Dec 2022	Checked By:	
Scale: 1:200@A3 1:2500@A3	Project No: 2223296	Dwg No: 01	Rev: Preliminary

54 Cae Gwilym Lane