

Trees (all Standard size)	Height	Size
Qr - Quercus robur (English Oak)	3.0m	25-45L

Native mixed hedge. Corylus avellana, Acer Campestre
50%-50% Density 5/m

PLANTING
All plants and planting to comply with the requirements of all current/relevant British Standard Specifications including BS 3336 Part 1 1992, Part 11 1990 and Part 1V 1984, where applicable BS 4428: 1989 and the Ball/L/Nursery Trade tender Document (th Edition: 1986) All plants to be supplied in accordance with the indicated schedule.

MAINTENANCE
Regular visits (minimum 12 No) required to maintain all planted areas in a weed and litter free condition using a combination of chemical spray and hand weeding to be agreed with the landscape Architect.

Maintenance to include watering, pruning pest and disease control and remulching as required. Grass mowing at 2 week intervals during growing season.

Structural planting areas shall be maintained as 'bare earth' non competitive weed free enviroment by repeated application of a glyphosate based herbicide.
Forisstant weeds and unwanted shrub shall be spot treated as necessary with an alternative herbicide to be agreed with the Landscape Architect.

Watering shall be carried out as described following any five day period without rain or as required by the Landscape Architect.

NB. Final visit to be immediately prior to handlning over and include a fertiliser treatment of Enmag (6:20:10) at 100g/m2 and 25mm depth bark mulch top up to all planted areas.

FULL SPECIFICATION
Shall prevail in the event of any discrepancy with this summary.

NOTES REGARDING IMPLIMENTATION WORKS TO BE CARRIED OUT ETC

implmentation timetables shall be the first planting season following completion of construction of the part of the site prior to occupation.

The works will be completed fully before occupation of any part of the development. Planting and trees shall remain as approved by Local Planning Authority for 5 years after approved date and if damaged will be replaced with others of same species.

PLANT MATERIAL TREATMENT
NB. All to be British Grown stock and fully hardend off.

Root Dip - Alignure Root Dip (1-3 solution) applied to all bare rooted stock (1) at time of lifting Nursery and (2) prior to planting.


Anti-Desiccant - with proof S800 to be applied to foliage of all containerised rootballed material in leaf, specimen conifers and evergreens etc.
(1) prior to transportation and
(2) during any delay planting.

Pruning - Allow for Pruning of all deciduous shrubs by 1/3rd following planting at landscape architects direction in the Planting Schedule.

New Hedge planting - New hedges are to be planted in two staggered rows, rows 300mm apart and plants within rows 400mm apart. Allow for 5 plants per linear metre. Plant in small single species groups to prevent competition between the species. Holly and larger growing trees are to be planted individually.

Immediately after planting cut hawthorn down to 150mm. If rabbits are a problem use shrub guards to protect plants, these are larger in diameter than spiral guards and so allow low lateral growth to develop. In the first spring after planting trim all lateral branches back by 50% (not holly). Prune damaged, diseased or dead wood immediately after first leaf break. Follow with a light trim every second or third year, allowing the hedge to increase in size each time. Replace dead, dying or damaged stock with the same species as soon as practicable in the first planting season following failure.

Check regularly that the shrub guards are sound and secure, and replace as necessary.



Ordnance Survey, (c) Crown Copyright 2023. All rights reserved. Licence number 100022432

AA

BB

BB

AA

Proposed
Building

AA Woodstone Harleeh Bat Box

BB Woodstone Salamanca Nest Box for:-
28mm hole nest boxes will be used by Tree Sparrows,
Blue Tits, Coal Tits and Great Tits.
32mm hole nest boxes will be used by Great Tits,
Pied Flycatchers, Tree Sparrows and House Sparrows.
The Oval entrance hole can be used by all suitable
species but is particularly good for House Sparrows
and Redstarts

Revision:

-

Sean Caddick Architectural

13 Belvidere Walk
Shrewsbury
SY2 5LT

[email: seancaddick@live.co.uk](mailto:seancaddick@live.co.uk)

Tel: 07971 166529

Client:

Mr M Mottershead

Project:

Proposed Agricultural Building
The Brook,
Ty Broughton

Drawing title:

Landscaping and Ecology

Scale:

1:500 @ A2

Date:

January 2024

Drawing number:

23/2424/02

Revision:

-