



Appendix D: Schedule of Arboricultural Supervision

Task	Action Required
Installation of tree protection barrier.	Arboricultural Consultant (AC) to check and confirm alignment and specification of tree protection barrier at point of installation. Make adjustments if required. Completion report to be retained on record, with photos, by AC and provided to LA Tree Officer upon request.
Excavation of foundation area to the south of the existing building.	AC to oversee trench excavation hatched blue on Tree Protection Plan and ensure the instructions provided on the Tree Protection Plan are followed. General site checks will also be undertaken at this point to ensure AMS is being followed. Completion report to be retained on record, with photos, by AC and provided to LA Tree Officer upon request.
Confirm fencing can be removed on completion of all works	AC to review site and confirm tree protection barrier can be removed, following all works.