



Sirius Planning Ltd
4245 Park Approach
Thorpe Park
Leeds
LS15 8GB

0113 264 9960
www.thesiriusgroup.com

Wrexham Council
Planning Department
16 Lord Street
Wrexham
LL11 1LG

Date: 21/03/2022

Our Ref: TFE1002

Dear Sirs,

PLANNING APPLICATION FOR THE CONSTRUCTION AND OPERATION OF AN ELECTRIC CHARGING FACILITY INCLUDING FOOD AND DRINKS KIOSK ON LAND TO THE SOUTH OF MINERS ROAD, LLAY INDUSTRIAL ESTATE, WREXHAM.

SEDG (Miners) Ltd (an SPV of Terra Firma Energy Ltd) are submitting an application for planning permission for an Electric Vehicle Charging Facility (EVCf) comprising of 10 charging points and bays, a food and drinks kiosk and associated infrastructure to the south of Miners Road, Llay Industrial Estate, Wrexham.

The application site is situated within Llay Industrial Estate and comprises an area within a wider industrial plot, which was previously used as a storage facility for a road haulage business. The application site measures 701m².

Much of the wider site comprises habitats of negligible to low ecological value including hardstanding and bare ground devoid of vegetation.

The entire wider site (land under applicants' control, illustrated on the submitted Drawing No. TFE1002/01/02) includes existing planning consents for a Reserve Power Plant (RPP) including a 9.9MW (P/2018/0797) and a 9.95MW (P/2018/0798) extension.

Under planning permission P/2018/0797 for the approved RPP, a working area for the entire landholding was defined and ecology mitigation, in the form of a Great Crested Newt mitigation strategy, was previously agreed. The previously approved GCN mitigation strategy for the adjacent RPP and the previously approved RPP site layout illustrating the site's working area accompanies this letter. The GCN mitigation strategy for the wider site has been implemented.

The proposed EV Charging facility area already has planning permission for an RPP, however the RPP facility has been reconfigured to enable the EV Charging facility to be developed. Separate Section 73 planning applications (application references P/2022/0200 and ref. P/2022/0199) have been submitted to amend the site layouts of the consented RPP, in order to accommodate the proposed EV Charging facility in the identified 'working area' of the site. Drawing No's. TFE1000/01/03 and TFE1001/01/03 attached to this letter illustrate the proposed RPP site layouts.

The proposed EV charging development is illustrated on submitted Drawing No. TFE1002/01/04 and proposed to only utilise part of the site within the previously approved RPP facility and defined working areas for the site. Therefore, the proposal would have no additional impact on ecology and

biodiversity beyond that previously assessed.

Should you have any queries relating to this matter, please do not hesitate to contact me.

Yours faithfully,

Francesca Wray
Senior Planner
Francesca.Wray@thesiriusgroup.com
0113 264 9960
For and on behalf of Sirius Planning Ltd


Enc:

Previously approved Reserve Power Plant Layouts illustrating approved working area for the site, Drawing No. SRE1065/17/03 R5 (planning application reference P/2018/0797)

2018 Approved Site GCN Mitigation Strategy

Proposed Reserve Power Plant Layouts, Drawing No's. TFE1000/01/03 & TFE1001/01/03 (S.73 planning application references P/2022/0200 & P/2022/0199)

Proposed EV Charging Facility Layout Drawing No. TFE1002/01/04



THIS INFORMATION IS CONFIDENTIAL AND THE PROPERTY OF SIRIUS. IT IS RELEASED ON CONDITION THAT NONE OF THE INFORMATION SHALL BE DISCLOSED TO ANY THIRD PARTY OR REPRODUCED IN WHOLE OR PART WITHOUT THE PRIOR CONSENT IN WRITING OF SIRIUS.

KEY

- EXISTING CONTOUR
- PROPOSED 2.4m HIGH PALASADE SECURITY FENCE
- PROPOSED 2.4m HIGH PALADIN SECURITY FENCE
- PROPOSED 1.8m HIGH WOODEN POST AND MESH FENCE
- PROPOSED POINT OF ELECTRICAL EXPORT CONNECTION CABLE ROUTE
- PROPOSED POINT OF GAS CONNECTION PIPE ROUTE TO GAS GOVERNOR
- EXISTING VEGETATION / TREES TO BE RETAINED
- EXISTING COMPACTED GRAVEL HARDSTANDING AREAS
- RELOCATED RUBBLE PILE
- EXISTING RUBBLE PILE TO BE RETAINED
- EXISTING SHORT GRASS / SCRUB VEGETATION
- MITIGATION COMPENSATION AREA
- AREA FOR POTENTIAL BATTERY STORAGE EXPANSION
- PROPOSED HARDCORE ACCESS TRACK
- PROPOSED GRAVELLED AREAS
- PROPOSED DNO SUBSTATION
- PROPOSED CUSTOMER SUBSTATION
- PROPOSED SWITCH / METER ROOM
- PROPOSED GAS GOVERNOR
- PROPOSED TRANSFORMER
- PROPOSED LUBE OIL CONTAINER
- PROPOSED GENERATOR WITH ROOF MOUNTED AND FLOOR MOUNTED COOLER OPTIONS

5	PLANT LAYOUT REVISED	19/9/18	S.T
4	PLANT LAYOUT REVISED	11/9/18	S.T
3	ECOLOGY AREAS AND FUTURE BATTERY AREAS ADDED	18/4/18	S.T
2	BOUNDARY FENCE AMENDED. ADDITIONAL BATTERY UNITS ADDED. FUTURE BATTERY AREA ADDED.	8/12/17	S.T
REV	DESCRIPTION	DATE	BY

CLIENT

4245 Park Approach, Thorpe Park, Leeds. LS15 8GB. 0113 264 9960

JOB TITLE

MINERS ROAD RPP FACILITY

DRAWING TITLE

INDICATIVE SITE LAYOUT

DRAWN	DATE	APPROVED	DATE
S.T	19/9/2018	J.B	19/9/2018
SCALE	SHEET	DRAWING NUMBER	REVISION
1:500	A3L	SRE1065/17/03	5

Miners Road RPP Facility – GCN Mitigation Strategy

Introduction

The proposed Reserve Power Plant (RPP) Facility on the south side of Miners Road, Llay Industrial Estate comprises a 0.52 ha brownfield site which in recent years has been used for the temporary storage of vehicles, shipping containers and stockpiled materials.

No ponds are present within the Site, but there are known Great Crested Newt (GCN) populations to the north (Police Site) and south (Former Llay Colliery). The Miners Road Site has the potential to act as a stepping stone between these two breeding populations, providing terrestrial habitat for foraging and migrating GCN.

The Site currently comprises the following habitats/land uses:

- An area of compacted hardcore and gravel in the north of the Site (0.17 ha). This is unfissured and contains no potential places of shelter for GCN. However, the topography allows shallow ephemeral puddles to form during wet weather and these may provide temporary refuges for GCN, for example during migration periods. A number of old vehicles and shipping containers are currently stored around the perimeter of the hard standing area. These have limited scope for GCN to shelter beneath them.
- Several rubble piles of varying sizes, including a large area in the south of the Site (0.05 ha) and a smaller discrete pile in the north west. Parts of the larger rubble pile are long established and the rubble is partially covered in mosses and vegetation growth. These areas have a high potential to support sheltering/hibernating GCN.
- The remainder of the Site, including the northern and western boundaries and the area to the south of the hardstanding, comprises a mix of short grass, ephemeral vegetation and scrub (0.29 ha). These areas could be used by GCN for foraging and/or migration.

A site meeting was held with NRW on 1.2.18 to discuss a potential mitigation and compensation scheme for the Site with respect to GCN. Following further internal discussion, the scheme outlined in this document is proposed.

Potential impacts on GCN

The Site has no potential to support breeding GCN as no ponds are present. The compacted hardstanding area has very limited potential to provide habitat for GCN, apart from on an ad hoc basis during wet periods, on migration etc. GCN could use the longer established rubble piles, particularly the large pile in the south west corner, for shelter and hibernation and the areas of grassland and scrub may be used for foraging purposes. No GCN have been found during terrestrial searches, but there is a risk that GCN could be present at the time of development or could enter the Site during construction or operation. The following potential impacts on GCN have been identified:

- Killing, injury or disturbance to GCN during construction.
- Damage or destruction of resting places when the Site is cleared for construction.
- Incidental killing, injury or capture during operational phases.

A mitigation/compensation scheme is therefore proposed in order to minimise the potential impacts on GCN and to satisfy the Habitats Directive derogation purpose (“imperative reasons of overriding public interest”) and two tests (“no satisfactory alternative”) and (“favourable conservation status”).

The mitigation scheme needs to ensure that the potential impacts on GCN are minimised through the implementation of the mitigation hierarchy (avoid, mitigate or compensate), but at the same time it should be proportionate to the identified level of impact and the quality of the affected habitats. In this instance, the Site is a previously developed brownfield site with a large proportion of the area to be developed being compacted gravel; the potential GCN interest has only developed at the site margins as a result of the stockpiling of materials and the lack of recent active vegetation management.

We propose that the mitigation scheme should therefore focus on avoiding disturbing the longest established rubble piles, as far as possible, together with providing an area of compensation land designed to maintain links between the northern and southern populations and avoid any fragmentation effects. A GCN licence would also be obtained to facilitate the exclusion and relocation of any GCN present within the development footprint during construction.

Outline of proposed mitigation/compensation scheme

It is proposed that the scheme should comprise the following key elements, as shown on the accompanying plan:

1. Site design/layout designed to minimise the impacts on GCN habitat.
2. Provision of a peripheral compensation area (~0.1 ha), incorporating part of the larger rubble pile and areas of scrub and grassland.
3. Retention of the remainder of the large rubble pile and partial retention of ephemeral vegetation/grassland outside of the fenced compound.
4. Implementation of a licensed mitigation scheme to capture and translocate any GCN within the development footprint.

Site design/layout

The selected layout concentrates the footprint of the facility on the existing hardstanding, the area used for equipment storage and the ephemeral/short grass habitats in order to minimise the impacts on places of shelter potentially used by GCN.

Other design features which will avoid or minimise impacts on GCN include the following:

- Avoiding the use of gullypots.
- The Site will be permeable to GCN once construction is complete (open site design with gravel; all fences will be permeable to GCN).
- The Site will not contain any structures which could kill, injure or capture GCN.

- There will be no need for permanent exclusion fencing.

Compensation area

The ~0.1 ha compensation area will be located outside a 1.8m high wooden post and mesh fence in two linked strips along the western and southern boundaries. The location of the compensation area is designed to maintain connectivity between the northern and southern GCN populations and to avoid fragmentation impacts.

Part of the existing large rubble pile will be within the compensation area, and the remainder comprises existing scrub and ephemeral/short grass vegetation.

The compensation area will be encouraged to develop scrub and dense vegetation naturally in order to provide enhanced habitat/shelter for GCN. The smaller rubble piles that lie within the development footprint will be relocated into the compensation area under the provisions of a derogation licence.

Retained habitats

The remainder of the large rubble pile will be retained outside the proposed 2.4m high Paladin security fence. Part of the existing ephemeral/short grass vegetation will also be retained outside the security fence. These areas will be left undisturbed to provide continued terrestrial habitat and resting places for GCN.


Licensed mitigation scheme

It is envisaged that targeted GCN surveys will not be required to inform the GCN licence application given that no ponds will be impacted and existing survey data are available for the off-site populations to the north and south.

The licensed scheme will include the following key elements:

- Confirmation of mitigation and compensation provisions, as outlined above, including retention of the large rubble pile.
- Details of a trapping and translocation scheme to capture and move any GCN present within the construction footprint. This will include:
 - Exclusion fencing.
 - Pitfall traps/refugia.
 - Minimum of 30 days trapping period in suitable weather conditions.
 - Details of where captured animals will be released (i.e. into retained habitats).
 - Relocation into the compensation area of smaller rubble piles within the construction footprint.
- Long term provisions for management and security of retained and compensation habitats, including:

- Management proposals, to include measures to maintain and enhance the structure of the habitats within the compensation area throughout the life of the development (25 years).
 - Monitoring of retained and compensation terrestrial habitats.
 - Aquatic habitat monitoring is not proposed, as all breeding ponds are off-site and not affected by the proposals.
- Biosecurity risk assessment, to include:
 - Appropriate measures to control any INNS found on site (NB none have been recorded to date); and
 - Measures or actions to prevent any INNS being introduced to/becoming established on the site during construction or operation of the scheme.
- Ecological compliance audit. This will identify Key Performance Indicators (KPIs) that will be used for the purposes of assessing and evidencing compliance with the agreed mitigation and compensation scheme.



THIS INFORMATION IS CONFIDENTIAL AND THE PROPERTY OF SIRIUS. IT IS RELEASED ON CONDITION THAT NONE OF THE INFORMATION SHALL BE DISCLOSED TO ANY THIRD PARTY OR REPRODUCED IN WHOLE OR PART WITHOUT THE PRIOR CONSENT IN WRITING OF SIRIUS.

- KEY**
- PLANNING PERMISSION BOUNDARY REFERENCE P/2018/0797
 - EXISTING CONTOUR
 - PROPOSED 2.4m HIGH PALASADE SECURITY FENCE
 - PROPOSED 2.4m HIGH PALADIN SECURITY FENCE
 - PROPOSED 1.8m HIGH WOODEN POST AND MESH FENCE
 - PROPOSED POINT OF ELECTRICAL EXPORT CONNECTION CABLE ROUTE
 - PROPOSED POINT OF GAS CONNECTION PIPE ROUTE TO GAS GOVERNOR
 - EXISTING VEGETATION / TREES TO BE RETAINED
 - EXISTING COMPACTED GRAVEL HARDSTANDING AREAS
 - RELOCATED RUBBLE PILE
 - EXISTING RUBBLE PILE TO BE RETAINED
 - EXISTING SHORT GRASS / SCRUB VEGETATION
 - MITIGATION COMPENSATION AREA
 - PROPOSED TARMAC AREA
 - PROPOSED HARDCORE ACCESS TRACK
 - PROPOSED GRAVELLED AREAS
 - PROPOSED GAS GENERATOR
 - PROPOSED GAS GENERATOR SWITCHROOM
 - PROPOSED GAS KIOSK
 - PROPOSED TRANSFORMER
 - PROPOSED AUX TRANSFORMER
 - PROPOSED CONTAINER
 - PROPOSED OIL LUBE CONTAINERS
 - PROPOSED DNO BUILDING
 - PROPOSED KIOSKS (2m x 2m)

REV	DESCRIPTION	DATE	BY
-----	-------------	------	----

CLIENT



4245 Park Approach, Thorpe Park, Leeds. LS15 8GB. 0113 264 9960


JOB TITLE

MINERS ROAD S.73 PHASE 1

DRAWING TITLE

PROPOSED SITE LAYOUT

DRAWN	DATE	APPROVED	DATE
S.T	22/2/2022	F.W	22/2/2022
SCALE	SHEET	DRAWING NUMBER	REVISION
1:500	A3L	TFE1000/01/03	0



THIS INFORMATION IS CONFIDENTIAL AND THE PROPERTY OF SIRIUS. IT IS RELEASED ON CONDITION THAT NONE OF THE INFORMATION SHALL BE DISCLOSED TO ANY THIRD PARTY OR REPRODUCED IN WHOLE OR PART WITHOUT THE PRIOR CONSENT IN WRITING OF SIRIUS.

KEY

- PLANNING PERMISSION BOUNDARY REFERENCE P/2018/0798
- EXISTING CONTOUR
- PROPOSED 2.4m HIGH PALASADE SECURITY FENCE
- PROPOSED 2.4m HIGH PALADIN SECURITY FENCE
- PROPOSED 1.8m HIGH WOODEN POST AND MESH FENCE
- EXISTING VEGETATION / TREES TO BE RETAINED
- EXISTING COMPACTED GRAVEL HARDSTANDING AREAS
- RELOCATED RUBBLE PILE
- EXISTING RUBBLE PILE TO BE RETAINED
- EXISTING SHORT GRASS / SCRUB VEGETATION
- MITIGATION COMPENSATION AREA
- PROPOSED TARMAC AREA
- PROPOSED HARDCORE ACCESS TRACK
- PROPOSED GRAVELLED AREAS
- PROPOSED GAS GENERATOR
- PROPOSED BATTERY CONTAINER
- PROPOSED BATTERY SWITCHROOM
- PROPOSED BATTERY FIRE SUPPRESSION TANK

REV	DESCRIPTION	DATE	BY

CLIENT

TERRA FIRMA
SUSTAINABLE ENERGY SOLUTIONS

sirius Planning
4245 Park Approach, Thorpe Park, Leeds. LS15 8GB. 0113 264 9960

JOB TITLE


MINERS ROAD S.73 PHASE 2

DRAWING TITLE

PROPOSED SITE LAYOUT

DRAWN	DATE	APPROVED	DATE
S.T	22/2/2022	F.W	22/2/2022

SCALE	SHEET	DRAWING NUMBER	REVISION
1:500	A3L	TFE1001/01/03	0



MINERS ROAD

DISCHARGE
INTO
EXISTING
SEWER

THIS INFORMATION IS CONFIDENTIAL AND THE PROPERTY OF SIRIUS. IT IS RELEASED ON CONDITION THAT NONE OF THE INFORMATION SHALL BE DISCLOSED TO ANY THIRD PARTY OR REPRODUCED IN WHOLE OR PART WITHOUT THE PRIOR CONSENT IN WRITING OF SIRIUS.

- KEY**
- LAND UNDER APPLICANT'S CONTROL
 - PLANNING APPLICATION BOUNDARY (701m²)
 - PROPOSED 2.4m HIGH PALADIN SECURITY FENCE
 - EXISTING VEGETATION / TREES TO BE RETAINED
 - EXISTING SEWER EASEMENT / GCN COMPENSATION AREA
 - PROPOSED HARDCORE ACCESS TRACK
 - PROPOSED GRAVELLED AREAS
 - PROPOSED TARMAC AREAS
 - FUTURE PHASES 1 AND 2
 - PROPOSED FOOD AND DRINKS UNIT (10m x 3m)
 - PROPOSED BINS
 - PROPOSED EV CHARGING POINT
 - PROPOSED CHANNEL DRAIN
 - PROPOSED DRAINAGE PIPEWORK
 - PROPOSED DRAINAGE INTERCEPTOR

REV	DESCRIPTION	DATE	BY
-----	-------------	------	----

CLIENT



TERRA FIRMA
SUSTAINABLE ENERGY SOLUTIONS



4245 Park Approach, Thorpe Park, Leeds. LS15 8GB. 0113 264 9960

JOB TITLE

MINERS ROAD EV CHARGING

DRAWING TITLE

SITE CONTEXT

DRAWN	DATE	APPROVED	DATE
S.T	11/2/2022	D.B	11/2/2022
SCALE	SHEET	DRAWING NUMBER	REVISION
1:500	A3L	TFE1002/01/04	0

