

Estimate Summary



Site Type	STORES	Store Name	WREXHAM EXTRA
Store Number	3433	Supplier Name	Ground Control
Version No	V.3.2	Location	SITE
Area	EXTERNAL	Sub-Element	SHRUBS, BUSHES, TREES
Element	SOFT LANDSCAPING	Who requested it?	Jacob Keene
Works Order No	84415363	% of area to be replaced/repai	

Describe the works required

Removal of dead trees by Service yard
Removal of tree that was cut down
Cutting back of trees obscuring CCTV on overflow car park
Cutting back of shrubs in overflow car park
Topping of Lime Tree

Why do we need to do it? (e.g. mandatory or statutory, beyond economical repair)

Health and safety. CCTV Cameras being blocked by Tree branches

How will you do it? (e.g. How will you programme works to mitigate risks)

Tree team to cut down and remove the 2 Alder Trees located by the service yard CCTV. Log and remove the felled/fallen Lombardy Poplar and survey the remaining Lombardy Poplars to determine their integrity. Carry out a 2metre crown reduction of the Lime Tree marked on the attached site plan which is blocking the sight line of the CCTV. Perimeter of overflow car park. Remove the lower limb on the London Plane and crown lift to clear the sight line of the CCTV. Cut back the shrubs around the overflow car park. These works will be carried out by our

What are the risks? (describe any risks e.g. trade, the people)

The area will be cordoned off while the works take place





