



ARBOR VITAE

ECOLOGY • FORESTRY • LAND USE



PRELIMINARY ECOLOGICAL APPRAISAL

LAND AT TYN TWLL

Project name: Tyn Twll, Llanarmon Dyffryn Ceiriog, Llangollen,
LL20 7LH

Grid Reference: SJ12053449

Date: 09/09/2021

Prepared by: Phillipa Stirling MSc ACIEEM

Reviewed by: William Prestwood BSc Director

Requested by: Roger Parry and Partners

Contents

1	INTRODUCTION	2
1.1	BACKGROUND TO DEVELOPMENT	2
1.2	SCOPE OF SURVEY	2
1.3	KEY PRINCIPLES.....	2
2	SITE DESCRIPTION	3
2.1	LOCATION, LANDSCAPE, AND BACKGROUND.....	3
3	SURVEY METHODOLOGY	3
3.1	DESK STUDY	3
3.2	SITE SURVEY	3
3.3	PERSONNEL	4
3.4	CONSTRAINTS	4
4	SURVEY RESULTS	5
4.1	DESK STUDY	5
4.2	HABITATS ON SITE	6
4.3	ADJACENT HABITATS	6
4.4	PROTECTED SPECIES	6
5	EVALUATION OF RESULTS AND POTENTIAL ECOLOGICAL IMPACT	7
5.1	HABITAT ASSESSMENT	7
5.2	PROTECTED SPECIES ASSESSMENT	7
6	MITIGATION AND ENHANCEMENT	8
6.1	HABITAT MITIGATION.....	8
6.2	PROTECTED SPECIES MITIGATION	8
6.3	ECOLOGICAL ENHANCEMENT.....	9
7	CONCLUSIONS	10
	REFERENCES	11
	FIGURE 1 LOCATION. 1:50,000	12
	FIGURE 2 AERIAL PHOTOGRAPH	13
	FIGURE 3 EXISTING SITE PLAN	Error! Bookmark not defined.
	FIGURE 4 PROPOSED DEVELOPMENT PLAN	Error! Bookmark not defined.
	APPENDIX 1 PHOTOGRAPHS	15

1 INTRODUCTION

1.1 BACKGROUND TO DEVELOPMENT

Planning permission will be sought for the construction of two holiday cabins within an agricultural field at Tyn Twll.

Arbor Vitae were commissioned by Roger Parry and Partners to undertake a Preliminary Ecological Appraisal in order to assess the impact of the development on habitats and protected species.

1.2 SCOPE OF SURVEY

The survey is primarily designed to:

- Identify and record habitats and important ecological features on site;
- Evaluate the potential of the proposed development site to provide opportunities for protected species;
- Determine any likely impact which the development and landscape proposals may have on these.
- Identify opportunities for the enhancement of habitats and biodiversity features on site.

1.3 KEY PRINCIPLES

All ecological surveys conducted by Arbor Vitae Environment Ltd are underpinned by the following key principles, as outlined by CIEEM (2018):

Avoidance - Seek options that avoid harm to ecological features (for example, by locating on an alternative site).

Mitigation - Adverse effects should be avoided or minimized through mitigation measures, either through the design of the project or subsequent measures that can be guaranteed – for example, through a condition or planning obligation.

Compensation - Where there are significant residual adverse ecological effects despite the mitigation proposed, these should be offset by appropriate compensatory measures.

Enhancements - Seek to provide net benefits for biodiversity over and above requirements for avoidance, mitigation or compensation.

2 SITE DESCRIPTION

2.1 LOCATION, LANDSCAPE, AND BACKGROUND

Tyn Twll farm is located 3.5km north-west of the village Llanarmon Dyffryn Ceiriog, Wrexham (Figure 1). The farm sits within a steep sided valley through which flows the Nant Cwm-llawenog, flooding annually (Figure 2).

The proposed site faces a motor cross track on the opposite side of the valley and there is a large agricultural shed adjacent to the site. The proposals will include the installation of two holiday cabins and a new access track. There is an existing field access point at the south-west corner of the field, from the lane.

3 SURVEY METHODOLOGY

3.1 DESK STUDY

An initial desk study was composed to gain background information regarding any protected species or designations within the area. The main sources of information were MagicMap, Lle geoportal and NBN Atlas.

3.2 SITE SURVEY

A site visit was made on 23/08/2020. The survey was carried out in accordance with CIEEM (2017) best practice guidelines. The objective of the survey was to find and record any signs of use by protected species and to note the habitat features present.

An assessment of the available habitats both on and adjacent to the site led to consideration of the potential of the site for the following protected species:

- Badger
- Bats
- Breeding birds
- Great Crested Newt
- Otter

The survey methodology was tailored to evaluate the area for these species in the following ways:

Badger

An area within 50 metres of the site was closely searched for the following signs of badger activity:

- Setts,
- Tracks and footprints,
- Latrines,
- Snuffle holes.

Bats

The site was assessed in terms of its suitability to support bat species. Hedgerow habitat and nearby potential habitat were assessed and recorded and potential impacts from the proposals considered.

Breeding birds

The site was assessed in terms of its suitability to support breeding bird populations. Hedgerow habitat and nearby potential habitat were assessed and recorded.

Great crested newt

A desk study and a ground search were conducted to search for any areas of open water within 250 metres. Waterbodies were then assessed based on the Habitat Suitability Index for great crested newts (Oldham et al., 2000 and ARG UK, 2010).

Otter

Any water courses within the area and appropriate terrestrial land were searched for the following field signs:

- Spraint,
- Footprints,
- Feeding remains.

3.3 PERSONNEL

The survey was carried out by Phillipa Stirling MSc ACIEEM: Ecologist.

3.4 CONSTRAINTS

There were no constraints to the survey being carried out.

4 SURVEY RESULTS

4.1 DESK STUDY

The desk study found that within 1km of the site there were the following designations:

Name	Designation	Distance from site
Berwyn	SPA SSSI SAC	0.4km
Wood to the south-west	Ancient semi-natural woodland	0.35km
Fedw Ty'n twll	Ancient semi-natural woodland	0.3km
Fedw Cwm-bach	Ancient semi-natural woodland	1km
The search included Ramsar, SSSI, SAC, SPA, NNR and LNR. ¹		

Results from the desk study revealed that within a 1km radius of the proposed development site the following protected species have been recorded:

Species	Distance	Protection
Otter*	0.5km	European Protected Species, Wildlife and Countryside Act 1981.
Goshawk Marsh Harrier Hen Harrier Merlin Peregrine Falcon Hobby Red Kite Barn Owl	0.5-1km	Wildlife and Countryside Act 1981- Schedule 1.
*Record from 1976.		

¹ SSSI: Site of Special Scientific Interest, SAC: Special Area of Conservation, SPA: Special Protection Area, LWS: Local Wildlife Site NNR: National Nature Reserve, LNR: Local Nature Reserve.

4.2 HABITATS ON SITE

All habitats are classified using JNCC's Phase 1 Habitat Survey Handbook (JNCC, 2010).

Improved grassland

The site forms a small plateau between two steep banks, above and below. The site itself has been agriculturally 'improved' and the sward now consists of: Italian ryegrass, white clover, chickweed, broadleaved dock and common nettle. The field is grazed by sheep throughout the year. The wider site is stock fenced.

4.3 ADJACENT HABITATS

Conifer plantation

The east boundary of the site is a conifer plantation which houses extensive pheasant pens and feeders. The ground flora is therefore very limited.

Semi-improved acid grassland/bracken

The steep bank at the north boundary of the site is characterised by exposed rock, bracken growth and acid grassland species. Those recorded during the survey include: tormentil, sheep sorrel, bracken, foxglove and mat grass.

Individual trees

The lower bank below the site is also made up of semi-improved acid grassland but also has several individual trees growing including hawthorn and rowan.

Hedgerow

There is an old hawthorn hedge at the south-west boundary corner of the site which now consists of individual mature specimens.

4.4 PROTECTED SPECIES

Badgers

There are no historical records of badger at the site and no field signs were found within the search area or adjacent woodland block.

Bats

The site itself does not provide any potential roosting features and the adjacent conifer woodland does not appear suitable for roosting bats given no aged features are associated with the trees.

It is possible that bats are present in the landscape and could use the adjacent woodland for foraging and commuting within the landscape.

There are no records of bat species within 1km of the site although it is likely that several species reside in the wider area.

Breeding birds

The site offers no suitable habitat for breeding birds including ground nesting species. The adjacent woodland may offer some limited nesting in the higher branches but the ground flora has been removed entirely and offers very scarce resources.

Great Crested Newt

No ponds were identified within 250m of the proposed development site and therefore no further survey work is required with regard to this species.

Otter

This species has been recorded 0.5km from the site but the record was from 1976. This stretch of river remains shallow for much of the year with annual flooding through winter months.

From an initial inspection the river provides limited resting opportunities for otters and if this feature is in use by the species, it is likely to be on a temporary basis for commuting purposes.

5 POTENTIAL ECOLOGICAL IMPACT

5.1 HABITAT ASSESSMENT

The proposals will result in the loss of 0.09ha of improved grassland. The loss of this type of habitat on such a small scale will have a negligible impact upon the ecology of the landscape.

Improvements to the habitats on site will be made through the creation of a new species rich native hedgerow.

5.2 PROTECTED SPECIES ASSESSMENT

Badger

The survey revealed no signs of use by badger and there are no historic records of badger at the site. The proposals will have no impact on this species and no further survey work or mitigation is required.

Bats

The proposals will have no impact upon roosting sites or bats directly. Given the remote location of the site, it will be necessary to implement a Wildlife Sensitive Lighting Plan to ensure that an increased human presence does not adversely impact nocturnal wildlife.

Breeding birds

The site is unsuitable for nesting and the proposals will have no impact upon breeding birds.

Otter

The site to be built upon does not provide any suitable terrestrial opportunities for otter and no evidence of this species was found during the survey. The proposals will have no impact upon this species.

The Wildlife Sensitive Lighting Plan will ensure that this nocturnal species, if present, remains undisturbed by the presence of artificial lighting on adjacent land.

6 AVOIDANCE, MITIGATION AND ENHANCEMENT

6.1 HABITAT MITIGATION

The extent and habitat to be lost is negligible and mitigation will not be required.

6.2 PROTECTED SPECIES MITIGATION

Bats

Any artificial lighting will be designed with nocturnal wildlife in mind. The following measures will be incorporated into lighting plans for the site:

- Hedgerows and key habitat features including woodland and individual trees on the site will not be illuminated in order to retain dark movement corridors for nocturnal wildlife. Illuminance along these features should be below 0.2 lux on the horizontal plane, and 0.4 lux on the vertical plane.
- Any exterior security or decorative lights to be installed on the development site will be less than 3 m from the ground and fitted with hoods to direct the light below the horizontal plane, at an angle of less than seventy degrees from vertical, and shall not be fixed to, or directed at, bat boxes or gables or eaves.
- Security lighting will be set on motion sensors with short timers (<1 minute) and will be LED with a passive infrared trigger.

- Lighting must be less than 3 lux at ground level and there shall be no light splay exceeding 1 lux along buildings, eaves or roof or adjacent hedgerows or trees.
- External lights will be hooded and directed toward the ground to reduce upward light spill.
- A warm white spectrum will be adopted throughout the scheme to reduce blue light component (<2700Kelvin).
- Internal luminaires will be recessed where installed in proximity to windows to reduce glare and light spill. LED luminaires will be used internally where possible due to their sharp cut-off, lower intensity, and dimming capability.
- Luminaires will always be mounted horizontally with an upward light ratio of 0%.

6.3 ECOLOGICAL ENHANCEMENT

A new species rich native hedgerow will be planted along the south boundary of the field site to following the existing sheep netting. The hedge will include: hawthorn, blackthorn, hazel, holly, dog rose, wild privet and guelder rose.

In order to improve opportunities on site for bats and breeding birds, the following wildlife features will be installed into the adjacent woodland:

- 1x 2F Schwegler bat box (or similar approved). This must be placed at least 3m from the ground.
- 1x 1B Schwegler bird box (or similar approved). This must be placed at least 2.5m from the ground.

7 SUMMARY

Planning permission will be sought for the construction of two holiday cabins within an agricultural field at Tyn Twll.

Arbor Vitae were commissioned by Roger Parry and Partners to undertake a Preliminary Ecological Appraisal in order to assess the impact of the development on habitats and protected species.

The proposed site faces a motor cross track on the opposite side of the valley and there is a large agricultural shed adjacent to the site. The proposals will include the installation of two holiday cabins and a new access track. There is an existing field access point at the south-west corner of the field, from the lane.

The proposals will result in the loss of 0.09ha of improved grassland. The loss of this type of habitat on such a small scale will have a negligible impact upon the ecology of the landscape.

The survey revealed no signs of use by badger and there are no historic records of badger at the site. The proposals will have no impact on this species and no further survey work or mitigation is required.

The proposals will have no impact upon roosting sites or bats directly. Given the remote location of the site, it will be necessary to implement a Wildlife Sensitive Lighting Plan to ensure that an increased human presence does not adversely impact nocturnal wildlife.

The site is unsuitable for nesting and the proposals will have no impact upon breeding birds.

A new species rich native hedgerow will be planted along the south boundary of the field site to following the existing sheep netting. The hedge will include: hawthorn, blackthorn, hazel, holly, dog rose, wild privet and guelder rose.

In order to improve opportunities on site for bats and breeding birds, the following wildlife features will be installed into the adjacent woodland:

- 1x 2F Schwegler bat box (or similar approved). This must be placed at least 3m from the ground.
- 1x 1B Schwegler bird box (or similar approved). This must be placed at least 2.5m from the ground.

8 REFERENCES

- ARG UK (2010). ARG UK Advice Note 5: Great Crested Newt Habitat Suitability Index. Amphibian and Reptile Groups of the United Kingdom
- Bat Conservation Trust (2018) Bats and artificial lighting in the UK. *Bats and the Built Environment series*, Guidance Note 08/18. Institution of Lighting Professionals.
- CIEEM (2017) Guidelines for Preliminary Ecological Appraisal, 2nd edition. Chartered Institute of Ecology and Environmental Management, Winchester.
- CIEEM (2018) Guidelines for Ecological Impact Assessment in the UK and Ireland: Terrestrial, Freshwater, Coastal and Marine. Chartered Institute of Ecology and Environmental Management, Winchester.
- Collins, J. (2016) Bat Surveys for Professional Ecologists: Good Practice Guidelines (3rd edn). The Bat Conservation Trust, London.
- Hundt L (2012) Bat Surveys: Good Practice Guidelines, 2nd edition, Bat Conservation Trust.
- JNCC (2010) Handbook for Phase 1 habitat survey - a technique for environmental audit, ISBN 0 86139 636 7.
- Mitchell-Jones, T. (2004) Bat mitigation guidelines. External Relations Team, English Nature.
- Oldham R.S., Keeble J., Swan M.J.S. & Jeffcote M. (2000). Evaluating the suitability of habitat for the Great Crested Newt (*Triturus cristatus*). *Herpetological Journal* 10(4), 143-155.

FIGURE 1 LOCATION. 1:50,000





FIGURE 2 AERIAL PHOTOGRAPH



FIGURE 3 PROPOSED SITE PLAN



APPENDIX 1 PHOTOGRAPHS

	Existing field gate access to the site and old hawthorn hedgerow pictured.
	The site and conifer plantation.
	The site and steep bank dominated by bracken and semi-improved acid grassland.





The river at the basin of the valley.



Dense conifer woodland with sparse ground flora.

