

Planting Specification

Trees and shrubs planted shall comply with BS.3936 (Specification of Nursery Stock) and shall be planted in accordance with BS.4428 (General Landscape Operations) and BS8545:2014 ' Trees from nursery to dependence in the Landscape'.

Woodland Enhancement Scheme to be read alongside 'Woodland Management Plan'

Bare root and root-balled stock to be planted in the dormant season.
All planting stock to be clearly labelled on delivery with the full botanical name. Plant stock to be approved prior to delivery to site and planting and trees be set out by Landscape Architect. All topsoil to be of good quality AS-DUG in accordance with BS 3882:2015. Depths of topsoil (Turf -150mm), (Shrubs- 300mm), Hedgerows (350mm) over free draining subsoil.

Organic soil improvement compost to be dug into all planting areas and used at 1cubic m per 10m2. All planting beds to be mulched in 75mm depth medium grade bark mulch immediately after planting.

If very wet or very dry conditions are found in proposed planting areas the landscape architect shall review planting locations and/or species.

Tree pits to be dug 400mm larger than rootball in any direction. Side and base of pit to be forked over to aid drainage help root establishment. Tree pit to be back-filled with a mix of:

- 1 part 'Melcourt topgrow' (or similar) tree planting compost;
- Mycorrhizal Fungi; and
- 3 parts good quality, as dug topsoil.

1m2 area of medium grade bark mulch to be placed at the base of each trees to a depth of 75mm. Mulch to be maintained at size and depth for two growing seasons.

Tree Stakes

3no. stakes and 3no. hessian/ rubber ties system to be used on each tree over 8cm girth

Single stake and 1.no rubber tree tie and spacer to be used on trees under 8cm girth.

Stakes to be 75mm diameter tanalised softwood and pointed at one end. Top of stake to be 600mm above ground level .

Stakes to be firm in ground, position stakes at time of planting,

Tree irrigation system to be provided to all trees.

Any queries in relation to planting schedules, layout or planting stock to be raised with Landscape Architect.

Suitable tree root barriers to be used on boundaries with hard-standing, walling, services, proposed and existing buildings.

Project:
Penley Hall Drive, Penley

Drawing Title:
Outline Specification for Planting

Scale: NTS	Date: 26/04/2022
Status: Planning	Drawn: ES Checked: TS
Drawing Number: 023.02.03	Revision: -