



# LANDSCAPING AND PLANTING SPECIFICATION

Mr Andy Cash  
Former Stables  
The Carriageway  
Heritage Way  
Tanyfron  
Wrexham  
LL11 5NS

## **PLANTING SPECIFICATION**

### **Planting**

All plants and planting to comply with the requirements of all current/relevant British Standard Specifications including BS8545:2014 and BS 3936: Parts 1, 4, 9 and 10 and BS 5236: 1975 where applicable; BS 4428: 1989; and the Bali/Li/Nursery Trade Tender Document (5th edition: 1986).

All plants to be supplied in accordance with the indicated schedule. All planting to be carried out within the first recognised planting season (November to March).

### **Plant Material Treatment**

All to be British Grown stock and fully hardened off.

Root Dip Proprietary root dip applied to all bare-rooted stock (1) at time of lifting at nursery and (2) prior to planting.

### **Watering**

Supply minimum 170 litres/standard or large feathered tree, 10 litres/transplant and 4 litres/shrub at planting.

### **Tree Guards**

Proprietary tree/shrub guards to be applied to all newly planted stock. All tree guards to be fixed to timber stakes in accordance with the manufacturer's recommendations. If container plants used provide 45 deg angle tree stake planted on side of prevailing wind with figure 8 tree tie. If bare root trees then use single upright stake with single trees

## **ESTABLISHMENT MANAGEMENT**

### **Tree and shrub areas**

Trees and newly planted hedges to be kept in a bare earth/weed free condition using repeated applications of a glyphosate based herbicide applied in accordance with manufacturer's recommendations. A 1m diameter weed free ring is to be maintained around each new hedgerow tree using repeated applications of a glyphosate based herbicide applied in accordance with the manufacturer's recommendations. Persistent weeds to be spot treated as necessary with alternative herbicides to be agreed with the Contract Administrator. Any plants affected by frost heave or wind rock shall be re-firmed. Fertiliser to be applied in accordance with the soil analysis recommendations. Any tree damaged or died within 5 years of planting to be replaced within the next available planting season.

### **Replacement Plantings**

Any tree/shrub losses during the first 12 months are to be replaced in accordance the original planning schedule and specification.

### **Tree Protection Fencing**

There are no existing trees on site which require protection.

## PLANTING SCHEDULE (ref to Plan 71063:1001 Rev B)

### Tree Planting

| <i>REF</i> | <i>Latin Name</i> | <i>English Name</i> |
|------------|-------------------|---------------------|
| T1         | Betula pendula    | Silver Birch        |
| T2         | Acer campestre    | Field Maple         |

## LANDSCAPING TREES AND SHRUBS



T2 - Silver Birch  
10 – 12m / 4m spread



T6 - Field Maple (Acer)  
15 – 25m / 4 – 8m