

Kerrie
Wood Farm House
Breaden Heath
Whitchurch
Shropshire
SY13 2LQ
United Kingdom

Quotation

Quote Number: 83
Quote Date: 08/12/2021
Valid For: 30 Days
Account: KERR02
Quote Ref:

Qty	Description	Rate	Total
1	Supply and Install a Tricel Novo UK 12 person sewage treatment plant. Excavate the hole in the agreed location with the customer and construct a concrete base for the tank to sit on. Lower the tank onto the newly constructed base and back fill around the tank using C25 concrete. Supply and install 2.5mm armored cable and connect to the property using a fused spur, cable will be housed in a 50mm ducting for added protection. Locate existing soil pipe from the holiday Let and install a new 450mm inspection chamber and pipe to the new STP. Install a new soil pipe from the 2nd holiday Let and pipe to the newly installed inspection chamber. Install new drainage field that will be constructed of 400mm of 40mm gravel, 100mm perforated pipe then gravel filled above the pipe, visqueen membrane added to stop any soil washing into the gravel then trench back filled and garden reinstated. Pipe the outlet pipe from the STP to the drainage field. All surplus soil to be taken off site and any broken ground will be reinstated and made good. All work is carried out within current building regulations and installed as per manufacturers requirements. The drain field has been installed and is up to date with all current government regulations (BS6297:2007)	12,800.00	12,800.00

Total Net Amount: £12,800.00

VAT @ 20%: £2,560.00

Quote Total: £15,360.00