

Retaining wall.
Refer to Architects drawing
for further details

Timber Fence.
Refer to Architects drawing
for further details

Approx 26m Mixed Native Hedge.
Refer to planting schedule for
further details on species.

Opportunity to introduce wildflower
planting along the hedge and fence
boundaries.

Proposed Trees
Refer to planting schedule
for further details on species.

Drawing to be read in
conjunction with Architects
drawings with regards to layout
and boundary treatments

SCALE: 1:150@A3

PLANTING SCHEDULE

Trees					
Qty	Code	Botanical Name	Girth	Height cm	Specification
3	Bp	Betula pendula	12-14cm	350-425	RB; 3x; Extra Heavy Standard; clear stem 200cm
2	Qr	Quercus robur	12-14cm	350-423	RB; 3x; Extra Heavy Standard; clear stem 200cm

Mixed Native Hedge (MNH)						
Total length: 26m (planted in double staggered rows)						
%Mix	Qty	Botanical Name	Size in cm	Root Condition	Density / Spacing	Notes
15	20	Acer Campestre	60-90	B	5/m	1+1; Transplant
5	7	Cornus sanguinea	60-90	B	5/m	1+1; Transplant
15	20	Corylus avellana	60-90	B	5/m	1+1; Transplant
45	59	Crataegus monogyna	60-90	B	5/m	1+1; Transplant
10	13	Ilex aquifolium	60-90	B	5/m	1+1; Transplant
10	13	Prunus spinosa	60-90	B	5/m	1+1; Transplant

