SURFACE WATER MANHOLE SCHEDULE

MANHOLE REF	COVER LEVEL (m)	INVERT LEVEL (m)	OUTGOING PIPE SIZE	DEPTH TO INVERT (m)	DEPTH TO SOFFIT (m)	MANHOLE TYPE	CHAMBER DIA	COVER TYPE	REMARKS	REVISION
SWMH A	114.675	113.525	150	1.15	1.00	E	1350	D400		
SWMH B	114.500	113.275	225	1.23	1.00	E	1350	D400		
SWMH C	114.410	113.280	150	1.13	0.98	F	1050	D400		
SWMH D	114.170	112.435	300	1.74	1.44	B	1500	D400	OUTFALL TO OIL SEPARATOR	
SWMH E	114.130	111.810	300	2.32	2.02	B	1200	D400	CATCH PIT MANHOLE. INLET LEVEL 112.36. OUTLET 112.31. OUTFALL TO SOAKAWAY.	
SWMH F	114.000	112.535	225	1.47	1.24	E	1350	D400		
SWMH G	113.850	112.625	225	1.23	1.00	E	1350	D400		

FOUL WATER MANHOLE SCHEDULE

MANHOLE REF	COVER LEVEL (m)	INVERT LEVEL (m)	OUTGOING PIPE SIZE	DEPTH TO INVERT (m)	DEPTH TO SOFFIT (m)	MANHOLE TYPE	CHAMBER DIA	COVER TYPE	REMARKS	REVISION
FWMH 01	114.265	112.855	100	1.41	1.31	E	1350	B125		
FWMH 02	114.170	112.705	100	1.47	1.37	B	1200	D400		

GENERAL

1. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE SPECIFICATION
2. ALL DRAWINGS TO BE READ IN CONJUNCTION WITH THE RELEVANT ARCHITECTURAL AND STRUCTURAL DRAWINGS.
3. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
4. ALL LEVELS ARE IN METRES RELATIVE TO ORDNANCE DATUM.
5. ALL DIMENSIONS ARE TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF CONSTRUCTION

Rev	Date	Description	By	Chkd
P1	06/11/18	ISSUED FOR INFORMATION	SH	PSS

PRELIMINARY

Project
COSTA COFFE - NEW BUILD
PARK ROAD
RUABON

Client
THE HARRIS PARTNERSHIP

Job No.	Drawing No.	Revision	Scale 1: 100 UNO @ A2
8951/D/701		P1	Date OCT 2018
			By SH
			Chkd PSS
			A2

Drawing Title
DRAINAGE
GENERAL ARRANGEMENT OF
MANHOLE SCHEDULE

147 London Road South,
Poynton, Cheshire. SK12 1LG.
Tel: 01625 876040
Fax: 01625 850104
email: mail@swf.uk.com
www.swf.uk.com

SWF CONSULTING
CONSULTING CIVIL & STRUCTURAL ENGINEERS