

Proposed West (Side) Elevation



Proposed North (Rear) Elevation



Proposed South (Front) Elevation



Proposed East (Side) Elevation

EXTERNAL FINISHES

EXISTING BUILDING:
Walls - Render walls and stonework detailing to be retained. Any repairs to match existing.
Pitched Roof - Welsh slate roof to be retained. Any replacement slates to match originals.
Doors & Windows - Timber to be retained and repaired if possible. Any replacement timber doors or windows to match style and profile of originals.

PROPOSED EXTENSION:
Walls - Light coloured render
Pitched Roof - Welsh slate to match existing
Doors & Windows - Timber with paint finish
Curtain Walling - Proprietary glazing system
External canopy - Timber
Garage - Brickwork and render to match existing

U | A | N

NOTES

Do not scale from drawing, figured dimensions to be used only

All dimensions to be verified on site. Any discrepancies are to be reported to the relevant parties

The content of the drawing remain the copyright of **Architecture (North) Limited**, no reproduction without written consent

revision	description	drawn	check	date
A	Minor design amendments	AK	AK	03/05/21
B	Updated and issued for planning	AK	AK	28/06/21
C	External finishes note updated.	AK	AK	09/08/21
D	Proposed finishes notes amended to suit conservation officer's comments.	AK	AK	09/09/21

client: Chestnut Healthcare
address: 9 Grove Road, Wrexham
proj no.: 19-205

drawn: AP/RW
checked: AK
date: 27/08/20
status: PLANNING

scale: 1:100
size: A1
title: **Elevations as Proposed**
dwg no.: **19-205 EL03**
revision: D