Dimensions are not to be scaled from this drawing.

Revision	Date	Description	Initials

SUPERMARKET

Aldi Superstore

Access Road

Entrance

Car Park

Plas Coch

plas coch pub restaurant

yard

covered terrace

terrace

deliveries

ac

dk

Grass

24 bed lodge

play

B5101

PLAS COCH RD

Tarmac

Unable to trace gas main beyond this point. Ground Penetrating Radar(GPR) results proved inconclusive. Further investigation required with hand dug trials. Please excavate with care.

Unable to Lift(UTL) manhole within the road due to cover being sunk into the frame.

Unable to trace gas main beyond this point. Ground Penetrating Radar(GPR) results proved inconclusive and within shrubbery line. Further investigation required with hand dug trials. Please excavate with care.

Unable to trace gas main beyond this point. Ground Penetrating Radar(GPR) results proved inconclusive. Further investigation required with hand dug trials. Please excavate with care.

Unable to trace water main beyond this point. Ground Penetrating Radar(GPR) results proved inconclusive. Further investigation required with hand dug trials. Please excavate with care.

Unable to LIft(UTL) manhouse to junction with mains not continuing the cover

Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Min/Avg	Min/Max
Car Park	Illuminance	Lux	13.13	37	3	0.23	0.08

Luminaire Schedule				
Symbol	Qty	Label	Arrangement	Description
	2	A	SINGLE	70w CDM-TD Aludra floodlight column mounted at 5m
	7	D	SINGLE	20w LED Deco Bollard

Kingfisher Lighting

For our LED lighting designs a 0.9mf has been used. If this differs from the maintenance period for this project then you must advise us accordingly

Members Of

HEA Highway Electrical Association

HEMSA

ILP Institution of Lighting Professionals

SELECT Ancillary Contractor

Kingfisher Lighting Ltd, Ritcher Way, Crown Farm Industrial Park, Mansfield, Nottinghamshire, NG19 8FJ
Tel: 01623 415 940 Fax: 01623 415 900
ld@kingfisherlighting.com www.kingfisherlighting.com

Project Title

Marstons - Proposed Lodge
Plas Coch - Wrexham

Scale	Project No
1:200 at A1	D33372D
Date	Drawing No
12/4/2018	D33372/AE/D

A lighting applications design service is provided by us in good faith and without charge, relating to Kingfisher products only. As such, whilst every endeavour is made for accuracy from information provided by yourselves, the final responsibility for the suitability of the design lies with the client. The company cannot, therefore, accept any liability or consequential loss incurred.

Lighting Designer - A Eldred