Timber play equipment

Native Planting

Swale

Wildflower Planting

LEGEND

Existing Trees and Hedges to be Retained
Trees to be retained and protected in line with BS5837:2012. Please refer to Ascerta Arboricultural Method Statement drawing no. P.906.17.01 for more information.

Proposed Trees in POS
Extra Heavy Satndard, 14-16cm girth, 4.5-6.25m high to be planted with a double timber stake secured with a rubber tree tie.

Ornamental Shrub Planting
Proposed shrubs and flowering herbaceous plants to be planted as 5-10L pots at 3 per sq.m. planted with feature specimen, 10-12L pots Species include: Hebe 'Red Edge', Choisya ternata, Potentilla fruticosa, Photinia x fraseri 'Red Robin'.

Proposed Native Hedgerow
Proposed native hedge to be 100-120cm height planted in a double row 300mm apart. Species include: Crataegus monogyna, Corylus avallana.

Proposed Grass - POS
Grass within POS to be seeded with heard wearing grass mix.

Proposed Bulb Planting
Planting along access track and POS areas for seasonal interest.

Proposed Species Rich Grassland
Lawn to be seeded with Emorsgate EL1 Flowering Lawn mixture or similar approved.

Proposed Native Plant Mix
To be whip planting, 60-80cm height at 2 plants per sq.m. Species include: Viburnum opulus, Crataegus monogyna, Rosa canina, Cornus sanguinea.

Proposed Footpath
To be coloured or black tarmac with pin kerb.

Proposed 450mm Knee Rail

Proposed Timber Play Equipment
To be located around POS area. E.g. Monkey bars, stepping logs, wobble bridge, log train.

GENERAL NOTES

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
7. All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
8. All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

Rev	By	Description	Date
C	MW	Site Plan revised	13.06.18
B	AB	Changed in line with client's comments	07.12. 17
A	AB	Changed in line with client's comments	01.12. 17

Client
Anwyl and Bellway

N

Project
Home Farm, Gresford Road, Llay

Description
Public Open Space - South Corner

Status
For Approval

Scale @ A1	Drawn	Checked	Date
1:250	MW	CT	07.12.17
Job number	Drawing number		Revision
2912	104		C

tpm landscape
chartered landscape architects
address: 4th Floor Studio 101 Little Lever St Manchester M1 1HR
tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk