PLANT SCHEDULE -
TREES

SPECIES	FORM	GIRTH	HEIGHT	ROOT	NOS
Acer campestre	EX H Standard	14-16cm	3.0-3.5m	Bare root	5
Acer rubrum	EX H Standard	14-16cm	3.0-3.5m	Bare root	6
Prunus avium	EX H Standard	14-16cm	3.5-4.5m	Bare root	9
Quercus robur	EX H Standard	14-16cm	3.5-4.5m	Bare root	1

SHRUBS

SPECIES	HABIT	FORM	SIZE	DENSITY (per mtr sq)	NOS
Ceanothus thyrsiflorus		3L	30-40cm	4	55
Euonymus fortunei 'Emerald Green'	Bushy	3L pot	20-30Dcm	4	33
Hebe "albicans'	Bushy	3L pot	20-30Dcm	4	30
Hedra helix		2L pot	20-30Dcm	8	80
Lavandula angustifolia 'Hidcote'	Bushy	3L pot	80-90cm	3	104
Prunus amanogawa		35L pot	2m-2.5m	Specimen	2

Hedge

Crataegus (Hawthorn)	60-80cm high, 0.4Ctr Double Staggered at 0.4ms offset	393
Fagus sylvatica (Beech Hedge)	60-80cm high, 0.4Ctr Double Staggered at 0.4ms offset	116
Prunus lusitanica	5L pot, 0.4Ctr Double Staggered at 0.4m offset	233
Ilex aquifolium (Holly)	5L pot, 0.4Ctr Double Staggered at 0.4m offset	83
Ligustrum Ovalifolium (Privet)	5L pot, 0.4Ctr Double Staggered at 0.4m offset	105

KEY

- Existing tree to be retained
- Existing hedge to be retained
- Existing tree to be removedl
- Proposed tree
- Proposed shrub
- Proposed hedge
- Proposed grass area - Turf or seedec
- Existing stone wall to be retained and remove railing
- Proposed stone wall
- Proposed 800mm high picket fence
- Proposed 1800mm high timber close board fence

GENERAL

THESE NOTES APPLY TO ALL PLANTING SHOWN ON THIS DRAWING.

PLANT MATERIAL
All Plants shall conform to relevant British Standards: BS 3936 and 5326.
All plants shall be true to form, type & size. They shall be healthy, vigorous, pest and weed free.
No substitutes in size or species shall be made without the written consent of the landscape architect.

TOPSOIL & SUBSOIL
Where requested a comprehensive analysis of a representative sample of topsoil is to be made and the results made available prior to it's use on site.
Laying general areas
Grass areas - 150mm depth top soil and 300mm ground broken further
Shrubs areas - 50mm mulch over 450mm depth top soil and 300mm ground broken further.
Tree areas - 75mm mulch over 750mm depth top soil and 300mm ground broken further
Subsoil formation levels shall be achieved under the main contract. The subsoil shall be ripped prior to spreading the topsoil layer.
Soiling Works - Subsoil and Topsoil spreading.
After settlement, finished topsoil levels should be 80mm below top of kerb to accommodate bark mulch. Topspoil in grass areas should be spread so as to be 20mm below any adjacent paved areas or kerbs after settlement to allow for turf. Generally finished soil levels shall be graded out to smooth running levels between all edges and fixed points. Subsoil formation shall be free draining and free from standing water/ waterlogging, prior to spreading topsoil to stated depths.
All debris shall be cleared prior to spreading soils . Spreading to be carried out in suitable weather, ie not when the ground is waterlogged or frozen or during heavy rain. Machines with a ground pressure of 0.26kg/ cm shall not be used and any ground consolidated by machine tracks shall be forked over to relieve compaction.
Landscape architect to agree any final levels, adjustments and grades as required.

TREE PLANTING
Trees shall be planted into prepared pits located as shown on the drawing - 900 x 900 x 750mm deep or larger to accommodate roots as required.
Break up base to a further depth of 150mm and ensure sides are not glazed. Backfill with a mix of 70% topsoil and 30% compost . (eg a Tree & Shrub planting product, well rotted farm yard manure or other composted green waste).
Staking: Trees to be double staked with 2nr 1.8m long stakes, treated and driven into the ground to leave 600mm above GL. Fix with 2 nr rubber ties and spacers at 600mm above GL. Trees 12-14cm girth or below to be fixed as above but with 1nr stake.
Ensure trees are planted at their original ground level and water thoroughly to ground capacity after planting.
All tree planting to be kept weed free during the maintenance and defects liability period.

SHRUB & HERBACEOUS PLANTING
Shrubs to be planted into prepared pits depth of 450mm located as shown on the drawing and to be backfilled with topsoil mixed with an approved slow release fertiliser such as Enmag general purpose to the manufacturers recommended rates.Break up base to a further depth of 150mm to aid drainage
Pits to be 75mm wider than the root spread and backfill gently, firming in around the roots.
Ensure shrubs are planted at their original ground level and water thoroughly to ground capacity after planting.
All shrub areas to be covered with a minimum 50mm well composted bark mulch and to be kept weed free during the maintenance and defects liability period.

Grass Areas
Ground Preparation Subgrade crossripped min.300mm deep at 300mm/cs. Remove stones and debris exceeding 50mm diameter.Cultivate existing topsoil. Additional top soil to be supplied and spread to make up level and to create even falls. Top soil to be cultivated to form a fine tilth prior to the laying of turf.

Turf
Recommendations for Turf for General Purposes'Supply and lay Rolawn Medallion turf or similar approved. Turf should be laid in autumn or early winter when the weather is open.Turf should not be laid in very hot, waterlogged, frosted, cold or drying wind conditions.If summer turfing has to take place the turfs should be saturated on delivery and kept lightly watered during the day until temperatures fall. In the winter turf should be
unrolled and laid out to prevent yellowing if it cannot be laid immediately. Turf to be supplied in rolls, not dried out or yellowed. Turf will be laid on the day of delivery. Turf rolls are to be undamaged without holes or torn or ripped edges. Turf grown on any nylon matting will not be accepted.Turf will be weed free and of a uniform size and thickness. Turf must be laid from suitably sized running boards. Walking over or standing on the turfs will not be allowed until fully established.

Seeded Grass
Fertiliser - Before final cultivation and three to five days before seeding/turfing. British Seed Houses pre seeding granular fertiliser mix no 2: N/P/K - 10/15/10% or similar approved. Coverage: Spread evenly at 70 g/m². After grading and fertilizing.
Seed bed: Reduce to fine, firm tilth with good crumb structure. - Depth: 25 mm. Rake to a true, even surface, friable and lightly firmed but not over compacted. Extend cultivation into any existing adjacent grassed areas sufficient to ensure full marrying in of levels.

MAINTENANCE
All planted areas shall be maintained in a clean and tidy condition with all litter and debris being removed at least once per month.

They shall also be maintained in a weed free state throughout the growing season by chemical or manual means
Maintenance items shall include: Weeding, pruning (as required), firming in after frost/human damage/high winds etc, control of pests and diseases, adjusting/ repairing tree ties as required and litter and debris removal.
All plants must also recieve adequate watering to ensure their health and survival.
A 70mm depth of well composted bark mulch is to be applied to all planted areas prior to handover.

TREE PLANTING MAINTENANCE
Annual maintenance to include 2nr visits to check ties and stakes and adjust where required

Rev	Details	Date	Drawn
B	Existing evergreen hedge removed and replaced along Rosemary Lane	19-05-14	AB
A	Full replan as per new layout and open space	18-03-14	AB

environmental associates
landscape architects -urban designers -environmental planners

Client: GORDON MYTTON HOMES

Project: Burton Hall Road - Housing Development

Title: PROPOSED LANDSCAPE BOUNDARY TREATMENT PLAN & PLANTING PLAN

Drawing No: EA/5236-100-01

Scale: 1@50@ A1 | Date: 15.11.13 | Revision: B

8 Abbey Square, Chester, Ch1 2HU, UK
Tel: 01244 311666
email: ea@environmentalassociates.net
web: www.environmentalassociates.net

© This drawing is subject to copyright