

Replacement trees provided along the boundary between the playing field and new access path

Playing Field

Tree Protection Fencing

CBff **Area of
No Dig
Construction**

Trees Retained

Rear gardens and areas of public open space are to be grass seeded and front gardens to be turfed where necessary.

**Approx
Location of
Drainage
Easement**

NEW NATIVE MIXED HEDGING TO BE FORMED IN THE FOLLOWING SPECIES:
CORNUS SANGUINEA 'MIDWINTER FIRE'
CORYLUS AVELLANA
CRATEAGUS MONOGYNA
ILEX AQUIFOLIUM
PRUNUS SPINOSA
ROSA PIMPFINEFOLIA
WHICH ARE TO BE MAINTAINED AT A HEIGHT OF 1200MM.

HEDGING SHOULD BE PLANTED IN TWO, STAGGERED ROWS AT A DENSITY OF NOT LESS THAN 5 PER METER , WITH APPROXIMATELY 450MM BETWEEN PLANTS IN THE SAME ROW, AND 300-400MM BETWEEN ROWS. THE WHIPS SHOULD BE PLANTED WITHIN THIS PATTERN IN GROUPS OF 2-3.

Anthony Eden Drive

Visibility Splay

Coed Aben

PLANTING LIST

SHRUBS/BUSHES

Bt-Bus sempervivens	'afruticulus'	10-30 4/m2
Cn-Crategeus monogyna	20-40 5/m2	
Cs-Cornus sanguinea	'midwinter fire'	40-60 5/m2
Ea-Eriolaia laticarpa	'yellow gold'	20-40 4/m2
Ec-Eucyrtos fortunei	'emerald in gold'	15-20 4/m2
Hh-Hedera Helix	40-60	
Hm-Humulus lupulus	20-40	
Ha-Hypericum androsaemon	40-60 4/m2	
Lc-Leucojum aestivum	40-60 4/m2	
Lv-Ligustrum vulgare	40-60 5/m2	
Ld-Laundaria angustifolia	'hidcole'	15-20 4/m2
Lr-Lonicera nitida	'purple heart'	20-40 4/m2
Lp-Lonicera pileata	'loughlin evergreen'	20-30 4/m2
Lc-Lonicera Perichrymum	'Graham Thomas'	60-90
Mh-Morone alba		
Mo-Mahonia aquifolium	'spallo'	20-30 4/m2
Pf-Pieris japonica	20-30 4/m2	
Rx-Rosa pimpinellifolia	40-60 5/m2	
Ro-Rosmarinus officinalis	'severn sea'	30-40 4/m2
Sr-Spiraea alba		
Sj-Siermia japonica	40-60 4/m2	
Sj-Siermia japonica rubra	40-60 4/m2	
Tc-Taxus canadensis	'Seaside'	20-30 4/m2
Ss-Saxifraga repens	20-30 4/m2	
Yb-Yucca filamentosa	40-60 5/m2	

0170-111X

Plant in specified bed at 6/m2

- *Galanthus nivalis* (Snowdrop)
- *Hyacinthoides nonscriptus* (Bluebell)
- *Narcissus pseudonarcissus* (Wild daffodil)

Turf mix as follows:

- 15.0 *Agrostis capillaris* Common Bent
- 15.0 *Anthraxanthum odoratum* Sweet Vernal Grass
- 35.0 *Festuca rubra* Red Fescue
- 10.0 *Dactylis glomerata* Cocksfoot
- 25.0 *Bromus tectorum* House Grass

NEW NATIVE MIXED HEDGING TO BE FORMED IN THE FOLLOWING SPECIES:
C3 - CORNUS SANGUINEA 'MIDWINTER FIRE'
C2 - CORYLIUS AVELANA
CRATEAGUS MONOGYNA
IL - ILEX AQUIFOLIUM
RD - ROSA PIMPFOLIA
WHICH ARE TO BE MAINTAINED AT A HEIGHT OF 1.70M TO MATCH THE HEIGHT OF THE STICK PROOF

Tree schedule
Ag - *Alnus glutinosa* 3no
Cbff - *Carpinus betulus* 'frans fontaine' 5no
Liquidambar styraciflua 4No
Sa - *Sorbus aria* 6no

New free

The contractor is to refer to the Tree Consultants drawings for the Root Protection Areas 2827/101

HL
I No
Climber and pit

Rev C 11.02.13 MP Planting to Public Opn space removed due to location of Attenuation tanks etc.

Rev B 15.11.12 MP Bulb and plug planting increased to the Southern part of the site over the attenuation tanks and drainage easement areas.
Rev A 14.11.12 MP Shrub planting adjacent to plots 8 and 9 revised to suit location of attenuation tanks.

	DRAWING STATUS:	FOR COMMENT

mm		ENGLAND BRISTOL	FOR SCOTTISH
mm		CLANGORS WREYHAM	

		GLAN GORS, WREXHAM

1424/SI/100 PLANTING PLAN

	SCALE	DATE	DRAWN	CHECKED	REV
	1:250@A1	Oct '12	MP	-	C