Existing Habitat

Health Centre

Existing Grassed area - regraded to suit new layout

Existing Tarmac Playarea - Regraded to suit new layout

Existing Tarmac Playarea showing indicative layout for pitches (No floodlighting will be installed)

Canopy Relocated from Existing Infants Scool

Existing Greenhouse

Existing Planting

Existing Slabs

PROPOSED INFANTS SCHOOL EXTENSION

EXISTING JUNIOR SCHOOL

Existing Planting

Existing car park redesignated as Tarmac Playarea

Existing Planting

Bow top fence & gates to play areas

Play Area

Grass

Existing trees

Grass

Play Area

Play Area

Main Entrance

Turning Head

Drop off Point

Proposed tree and shrub planting

Tarmac Playarea showing indicative layout for pitches (No floodlighting will be installed)

Proposed planting

Drop off Point

1.2m high bow top fence to car park area

2m high polyester coated weldmesh fence

Existing Road to be incorporated into School Site (Porous asphalt top surface laid over existing road)

2m high polyester coated weldmesh fence

Proposed location of Staff Car Park (A Separate Application will be submitted for these works to enable them to commence before the main works to the school)

Proposed tree planting

Benches

1.2m high bow top fence to car park area

Proposed planting

Existing oak in grassed area

Proposed tree and shrub planting

Indicative layout for Grassed Playing Fields (No floodlighting will be installed)

Proposed tree and shrub planting

2m high polyester coated weldmesh fence

SCHOOL ROAD

LLAY INFANTS SCHOOL

Scale Bar (metres)

Revisions:

A 20/07/10 Play areas amended, Car park amended, Canopy relocation from existing Infants, Alternative habitat area shown.

B 04/08/10 Notations added re car park (separate planning application), hard & soft recreation areas, road closure, drop off points. Boundary line corrected.

C 06/10/10 Areas of landscaping works shown. Car park area amended

WREXHAM COUNTY BOROUGH COUNCIL.

MARTIN WRIGHT, B.Sc.(Hons), MRICS.
CHIEF TRANSPORTATION AND ASSET MANAGEMENT OFFICER.
CROWN BUILDINGS, 31 CHESTER STREET,
WREXHAM, LL13 8BG.

Tel: (01978) 297102 Fax: (01978) 297103

Project: LLAY PARK PRIMARY SCHOOL

Detail: PROPOSED SITE PLAN

Drawn/Checked:	Date:	AutoCad File Ref: g:\work\area\see\ llay primary school\pd2009\046
SEE / KHJ	03/10	
Scale: SCALE BAR	Project No: PD2009/046	Dwg No: (G)01 Rev: C