

PENLEY Dust Prevention Policy.

Primesave will always carry out their projects causing minimum disruption and interference with the lives of all persons who may be affected. We realise that Construction work generates dust and utilise several procedures to minimise and if possible eliminate this problem.(see section 1.4.4 in the Construction Phase H&S Plan.) The main generators of Dust and operational procedures are listed below.

Excavations.

As the ground is disturbed in dry conditions dust may be generated. To keep this to a minimum, we spray areas with water to dampen down dust generation. Under windy conditions excavation work will be halted if the ground is very dry.

Roadways.

Movement of traffic over dry areas will generate dust. The roads will be dampened down by water spray regularly throughout each day. A Water Bowser will be kept on site for this purpose.

Loads on Vehicles.

All loads which are dry and hence possible dust generators will be sheeted before being moved on or off the site.

Mixing of Concrete etc.

Whenever products which are dusty are being mixed, the sequence of mixing will be arranged to eliminate excess dust.

Storage of materials.

All materials with the potential to produce dust under certain weather conditions will be covered with sheeting.

The Site Manager will remind all site personnel of Dust prevention measures at the morning briefings.