



Ground Protection:
The existing soft surfaced surrounds are to be protected during the roof works by (where possible) 2m of ground boards surrounding the garage footprint with pedestrian only access for roof works; no material storage allowed in soft surfaced areas.

- Site Welfare & Material Delivery & Storage - to use the existing hard surfaces and parking areas clear of the retained trees.

Tree Roots – the higher soil level of the trees' location to existing structures, and the garages retaining walls and foundations will have influenced tree root growth; standard circular RPAs have been augmented to omit RPAs from the garage footprints, but occupy the surrounding grounds (although the offsite conditions are favorable for tree root growth, tree root growth may also be restricted by the boundary wall).

 Tree Crown Spread
 Root Protection Area (RPA)
 Tree Stem
 T1 Tree No.
Tree Condition Category
 A
 B
 C
 U

The surveyed trees are illustrated on this Constraints Plan which is prepared in accordance with British Standard BS5837: 2012 'Trees in Relation to Design, Demolition and Construction – Recommendations'



Indigo^{Ltd}

Surveys

(Mail) Second Floor, 1 Hunter's Walk, Canal Street, Chester, CH1 4EB
 Telephone: 0333 123 7080 www.indigosurveys.co.uk

Drawing Number

20102/TPP/01

A3

REV.
/

The original of this drawing was produced in colour – a monochrome copy should not be relied upon.

THIS DRAWING IS CONFIDENTIAL AND MUST NOT BE REPRODUCED
WITHOUT THE CONSENT OF INDIGO SURVEYS LTD.