

12th October 2020

Simon Greenwood
Planning Office
Wrexham Country Borough Council

RE: Bridge repairs and refurbishment at Papermill Bersham

Dear Sir

As the structural engineer report states the brick arch of the bridge is functioning therefore I will omit the reinforced slab from the design. The report also states that the brick parapet walls are leaning out and require removing, also the stone copings laid on top (neither of which were original).

We have estimated the brickwork and copings to be approx. 5.75 tonne which would need to be removed from the arch.

I have attached the amended drawing to show the raised box beam and stone copings on top of the box beam.

I require the height of the railings or walls to be of sufficient height for the safe crossing of ourselves, family and the general public who use the bridge.

Kind Regards

Kevin Gough