

MANHOLE REFERENCE	MANHOLE TYPE	COVER LEVEL	INVERT LEVEL	DEPTH	NOTES
FW15	600 DIAMETER PPIC	81.000	80.147	853	-
FW16	600 DIAMETER PPIC	81.000	80.106	894	-
FW17	600 DIAMETER PPIC	81.000	80.018	982	-
FW18	600 DIAMETER PPIC	81.000	79.855	1145	-
FW19	600 DIAMETER PPIC	81.000	79.673	1327	-
SW13	600 DIAMETER PPIC	81.000	80.550	450	-
SW14	600 DIAMETER PPIC	81.000	80.104	896	-
SW15	600 DIAMETER PPIC	81.000	79.922	1078	-
MD-SHE-0076-2000-0350-2000	1500 DIAMETER CONCRETE	81.000	79.500	1500	HYDROBRAKE

MANHOLE SCHEDULE

SITE WIDE DRAINAGE WORKS

SCALE 1 : 250

A	Drainage Issue	IB	06/11/2019
REV	DESCRIPTION	BY	DATE
JP Structural Design			
PROJECT			
YSGOL BRO ALUN			
TITLE			
SITE WIDE DRAINAGE LAYOUT			
CLIENT			
LAWRAY ARCHITECTS			
DRAWN BY IB		CHECKED BY JP	DATE 10/17/19
SCALE (@ A1) As indicated		PROJECT NUMBER 49003	
DRAWING NUMBER 49003-JP-DR-S-5001			REV A