

[illegible]

	Existing Trees and Hedgerows to be Removed		Proposed Hedgerows Evergreen hedgerows to be planted in 5L containers at a rate of 3 per lin. metre.
	Existing Trees and Hedgerows to be Retained Trees to be retained and protected in line with B5587:2012.		Proposed Ornamental Shrubs Proposed shrubs and flowering herbaceous plants to be planted as 3-5L pots at 3-5 per sq.m. with individual specimen shrubs.
	Proposed Ornamental Trees Trees to be planted as 12-14cm girth, heavy standard, 3.5-4m high. Trees to be staked and secured with suitable rubber ties.		Proposed Grass To be turf off other than maintenance access strip on southern boundary to be seeded
	Proposed Small Ornamental Trees Trees to be planted as 10-12cm girth or multi-stem, 2-3m high and secured with double stake and suitable rubber ties.		Proposed Wildflower Meadow Mix To be Emorgate EM2 Standard General Purpose Meadow Mix, supply by Emorgate or similar approved. Sowing rate 4/gm2.
	Proposed POS Trees Trees to be planted as 14-16cm, extra heavy, 4.5-6m high with 2m clear stem. Trees to be staked and secured with suitable rubber ties.		

[illegible]

1. This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
2. This drawing is to be read in conjunction with detail landscape drawings, details and specification.
3. This drawing is to be read in conjunction with all relevant Architects', Engineers', Specialists, Bills of Quantities and Specifications.
4. The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
5. The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
6. All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.

Rev	By	Description	Date
A	GJC	Updates in line with architect layout	14.02.20

Status
For Approval
Scale @ A1 Drawn Checked Date
1:200 GJC MW 01.11.19
Job number Drawing number Revision
3455 202 A