

1. All dimensions to be verified on site prior to any shop works being commenced.
2. Any discrepancies to be reported to the Designer before any work is put in hand.
3. Do not scale from this drawing.
4. This drawing is to be read in conjunction with relevant consultants and specialists drawings.
5. This is a metric drawing.
6. Dimensions indicated thus "" are site dimensions and are to be adjusted onsite by the Contractor accordingly.



Both leaves of brickwork are to be tied together using suitable s.s. ties at ctrs not exceeding 450mm, both horizontally and vertically. Joint between the two leaves to be fully filled with mortar as the work proceeds.

SECTION THROUGH POST

FENCING NOTE:
To be to BS 1722: Part 5.
Height as shown and adjusted accordingly, as required.

Posts: Class A 100 x 100mm concrete (for non-exposed areas). Set out to suit fence panel (max. 2400mm ctrs.) to BS EN 12839.

Posts to be set in 300mm dia. x 750mm deep conc. filled hole to not less than half the depth.

Ensure fence panel has capping rail, twice splayed & rebated once for fixing.

All fittings & fixtures to be galvanised.

FRAME, LEDGED & BRACED GATE:
(boarded as fence - all to be confirmed by panel
manufacturer and adjusted accordingly)

Stiles: 94 x 63 fin.
Head: 94 x 63 fin.
Braces: 94 x 63 fin.
Mid Rail: 94 x 63 fin.
Bottom Rail: 144 x 63 fin.

IRONMONGERY:
Heavy duty gate ring latch (galv'd. finish).
Heavy duty steel butt hinges to BS 227:Part 1A.
(galvanised finish, sheradised screw fixed).
Heavy duty extended galvanised bolt to gates, positioned centrally on mid rail.
Heavy duty galv. drop bolts to double gates (drive access) with retainers to fix in open position.

FINISHES:
All timbers to receive suitable approved stain finish.
Colour to be agreed.

Provide 3-strand galvanised metal wire securely fixed to the external facing elevation at top, centre & bottom rail positions of fence panels.

Rev.	Description	Total	Chk
Client	Mr James Wilson	Dwg. Title	External Works AS PROPOSED
Project	19 - 20 Hill Street Cefn Mawr	Scale	1:20 Drawn C.B. Chkd. C.B. Date 16/04/18
		Dwg. No.	790/A(9)01
		Revision	-