



- Monthly checks for first 12 months to monitor water levels and plant development
- Photographs and summary to be sent to ecologist
- Quarterly accompanied checks by ecologist to ensure monitoring is undertaken as advised
- Replacement planting as required
- Review of hydrological feed as required. This may require feed from additional gravel filter drains

Reedbed Treatment System  
Phragmites to be cut in winter  
to 15cm. First cut anticipated in year 5.

Amenity/Landscape Grassland  
Mown weekly through the growing season  
will dissuade GCN from using.

**Retained Hedgerows H1 to H10**  
(Excluding H4 which will be lost)  
\* Cut on a sectional rotation every 2 years.  
Timed to avoid bird breeding activity and to maintain berries/ fruit availability  
\* Developing adjacent tree and shrub planting will restrict hedgerow management, as it develops and so may require cutting from adjacent fields.

Grassland Areas  
To be mown annually as per GCN specific habitat management plan.

Newly Planted Hedgerow  
Years 1-3 annual cut as per management plan and subsequent rotational management as per retained hedgerows.

Tree and Shrub Planting:  
Weed Suppression– annual treatment Years 1-3  
Replacement of dead/dying trees Years 1-3.

Penny Anderson  
Associates Ltd  
CONSULTANT ECOLOGISTS



**SECTION A-A' (scale 1:500)**

### Figure F1 Habitat Management Prescriptions



Landscape Architects

White House Farm  
Shocklach, Malpas  
Chester SY14 7BN  
Tel: 01829 250646  
Fax: 01829 250527  
Mob: 07809 029810  
[chris@chrisburnettassociates.co.uk](mailto:chris@chrisburnettassociates.co.uk)  
[www.chrisburnettassociates.co.uk](http://www.chrisburnettassociates.co.uk)

|                  |            |                                                                        |                                                                                       |
|------------------|------------|------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| Client           |            | <b>Aviagen</b>                                                         |                                                                                       |
| Project          |            | <b>Turkey Facility Llay: Landscape &amp; Visual Impact Assessment.</b> |                                                                                       |
| Scale            |            | <b>1:1,000 @ A1 (section A-A' 1:500)</b>                               |                                                                                       |
| Date             | Drawn      | Checked                                                                |  |
| 30/05/16         | JHD        | CB                                                                     |                                                                                       |
| Dwg No.          | Revision   |                                                                        |                                                                                       |
| <b>ALLP15.02</b> | <b>-04</b> |                                                                        |                                                                                       |