CARRIAGEWAY TO BE RESURFACED ON APPROACH TO STOP LINE WITH A PSV OF 68.

CONTRACTOR TO MAKE ALLOWANCE FOR LOCALISED TIEING IN OF KERBS AND SURFACING IN ALL AREAS AS NECESSARY AND TO THE SATISFACTION OF THE LOCAL AUTHORITY ENGINEER.

PROPOSED GUARDRAIL.

CONTROLLED CROSSING.

UNCONTROLLED CROSSING.

NEW GULLIES TO CONNECT INTO ON-SITE DRAINAGE NETWORK. EXACT CONNECTIONS TO BE REFERENCED FROM ON-SITE DRAWINGS BY OTHERS.

NEW SITE ACCESS JUNCTION TO PROPOSED RESIDENTIAL DEVELOPMENT.

CONTRACTOR TO ENSURE HB2 TO BN TRANSITION KERBS ARE LAID BETWEEN ALL FULL HEIGHT/DROPPED KERBS TO THE SATISFACTION OF THE OVERSEEING LA ENGINEER.

NEW GULLIES TO CONNECT INTO EXISTING GULLY TAILPIPE. CONTRACTOR TO CONFIRM LOCATION OF SEWER PRIOR TO CONSTRUCTION.

CONTRACTOR TO MAKE ALLOWANCE FOR LOCALISED TIEING IN OF KERBS AND SURFACING IN ALL AREAS AS NECESSARY AND TO THE SATISFACTION OF THE LOCAL AUTHORITY ENGINEER.

PRIOR TO COMMENCING WORKS THE CONTRACTOR IS TO ENSURE THAT INTERFACE LEVELS AND PAVEMENTS BETWEEN THE OFF-SITE S278 DESIGN AND INTERNAL ON-SITE DESIGN TIE IN AND ANY DISCREPANCIES SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER. ALL THRESHOLDS ARE TO TIE IN AND PAVEMENT/KERBING MADE GOOD WITH LOCALISED REPAIRS WHERE NECESSARY TO THE SATISFACTION OF THE OVERSEEING LA ENGINEER. CONTRACTOR TO CONFIRM ADEQUATE FALLS TO ADJACENT DRAINAGE AREAS PRIOR TO COMMENCING WORKS.
PLEASE REFER TO DEVELOPERS M&E DRAWINGS FOR DETAILS OF ANY ALTERATIONS TO EXISTING STATS EQUIPMENT. ANY STATS DIVERSION DETAILS SHALL BE PROVIDED TO LOCAL AUTHORITY FOR REVIEW. ALL EXISTING STATS COVERS AFFECTED BY THE WORKS TO BE RESET TO NEW CARRIAGEWAY LEVEL WHERE REQUIRED.

THE EXTENT OF REINSTATEMENT AND TYING IN TO BE AGREED ON SITE AS PART OF THE PRE-COMMENCEMENT MEETING FOR THE S278 WORKS.

EXISTING VRS BARRIER TO BE REMOVED IN VICINITY OF RIGHT TURN LANE. P4 END TERMINAL TO BE PROVIDED ON EXISTING VRS PRIOR TO THE RIGHT TURN LANE IN ACCORDANCE WITH CHAPTER 5 POINT 5.4 OF CD 377. SET BACK AND WORKING WIDTHS TO BE DETERMINED ACCORDINGLY TO MANUFACTURERS INDIVIDUAL REQUIREMENTS AND THE UNITS SHALL BE BS EN 117 COMPLIANT & INSTALLED WITH THE MANUFACTURERS REQUIREMENTS AND THE GENERAL DETAILS OF THE SPECIFICATION FOR HIGHWAY WORKS.

NEW GULLIES TO CONNECT INTO EXISTING GULLY TAILPIPE. CONTRACTOR TO CONFIRM LOCATION OF SEWER PRIOR TO CONSTRUCTION.

NEW GULLIES TO CONNECT INTO ON-SITE DRAINAGE NETWORK. EXACT CONNECTIONS TO BE REFERENCED FROM ON-SITE DRAWINGS BY OTHERS.

UNCONTROLLED CROSSING.

NEW SITE ACCESS JUNCTION TO PROPOSED RESIDENTIAL DEVELOPMENT.

CONTRACTOR TO ENSURE HB2 TO BN TRANSITION KERBS ARE LAID BETWEEN ALL FULL HEIGHT/DROPPED KERBS TO THE SATISFACTION OF THE OVERSEEING LA ENGINEER.

THE EXTENT OF REINSTATEMENT AND TYING IN TO BE AGREED ON SITE AS PART OF THE PRE-COMMENCEMENT MEETING FOR THE S278 WORKS.

NEW GULLIES TO CONNECT INTO EXISTING GULLY TAILPIPE. CONTRACTOR TO CONFIRM LOCATION OF SEWER PRIOR TO CONSTRUCTION.

FOOTWAY TO TIE INTO EXISTING.

CONTRACTOR TO MAKE ALLOWANCE FOR LOCALISED TIEING IN OF KERBS AND SURFACING IN ALL AREAS AS NECESSARY AND TO THE SATISFACTION OF THE LOCAL AUTHORITY ENGINEER.

NOTES

FULL DEPTH CARRIAGEWAY CONSTRUCTION(NO LIMESTONE AGGREGATE TO BE USED IN SURFACE COURSE) TO BE AS PER DESIGN DETAILS WITHIN TRANSPORT STATEMENT AS MATERIALS SPECIFICATION AND SURFACE COURSE TO BE AS PER SURFACE TREATMENT PLAN. ALL WORKS TO BE CARRIED OUT IN ACCORDANCE WITH CLAUSE 900 OF THE SHW.

SURFACE: 50MM THICK HRA 35/14 SURF 4/16D DES 20MM PRECOATED CHIPPINGS PSV MIN 60 TO BS EN 13108, MIN PSV OF 68 TO BE APPLIED ON APPROACHES TO ROUNDABOUT AND TRAFFIC SIGNAL STOP LINES.

BINDER: 60MM THICK AC 20 DENSE BIN 40/60 REC TO BS EN 13108.

BASE: 150MM THICK ACD BASE 40/60 REC TO BS EN 13108.

SUB BASE: MIN 150MM THICK SUB-BASE (SUBJECT TO ON-SITE CBR RESULTS-PLEASE REFER TO TABLE ON D004) IN TYPE 1 GRANULAR MATERIAL, LAID AND COMPACTED TO THE SPECIFICATION FOR HIGHWAY WORKS CLAUSES 701, 801, & 803.

CAPPING: REQUIRED CAPPING DEPTH SUBJECT TO ON-SITE CBR TEST RESULTS. FOR ALL CAPPING DETAILS PLEASE REFER TO THE TABLE PROVIDED ON THE STANDARD DETAILS PLAN AND THE DMRB FOR FURTHER GUIDANCE. CBR TO BE CARRIED OUT AT FORMATION LEVEL AND SHOULD BE SUFFICIENT TO REFER RESULTS TO A REPRESENTATIVE OF THE LOCAL AUTHORITY AND THE DESIGN MANUAL FOR ROADS AND BRIDGES VOLUME 7, SECTION 2, PART 3 CHAPTER 3 FOR FURTHER GUIDANCE ON SUB-BASE CAPPING RELATIONSHIP. APPROPRIATE TERRAM GEOTEXTILE MEMBRANE TO BE LAID BENEATH CAPPING LAYER TO MANUFACTURER'S PROPRIETARY REQUIREMENTS.

PLANE REQUIRED/SURFACE:
PLANE 50MM, BOND COAT IN ACCORDANCE WITH SHW AND REPLACE WITH 50MM/SURFACE COURSE AS SPECIFIED ABOVE, IN AREAS OF OVERLAY LEVELS TO BE MADE UP WITH REQUIRED DEPTH OF BINDER COURSE (MIN 80MM) PRIOR TO LAYING OF SURFACE COURSE.
ALL FULL DEPTH AND INLAY TO INCORPORATE 300MM STEPPED TIE IN CONSTRUCTION. PLEASE REFER TO ST-AND/07 DETAIL AS SUPPLIED.

MARRON WIDENING IN AREAS LESS THAN 2.0M
AS FULL DEPTH CARRIAGEWAY CONSTRUCTION BUT BASE AND SUB-BASE LAYER REPLACED WITH ST2 CONCRETE. PLEASE SEE STANDARD DETAIL ON DWG D004.

FOOTWAY CONSTRUCTION
40MM THICK AC10 DENSE BIN 160/220 TO BS EN13108-1.
60MM THICK AC20 DENSE BIN 160/220 TO BS EN13108-1.
100MM THICK TYPE 1 SUB BASE 100MM THICK TYPE 1 AT VEHICLE CROSSINGS.

KERBING
ALL KERBS, CHANNELS, FLAGS, EDGINGS ETC CONSTRUCTED TO THE REQUIREMENTS OF BS EN 1339,1340, BS 7533 AND BS 7263. ANY GAP BETWEEN KERB AND EXISTING CARRIAGEWAY TO BE FILLED WITH HOT POURED BITUMEN MAX WIDTH 20MM. WHERE THE GAP IS GREATER THAN 20MM IT SHALL BE REINSTATED AS SHOWN IN THE REINSTATEMENT STANDARD DETAIL. ALL KERBS TO BE BEDDED ON SURFACE COURSE, JOINTS TO BE SEALED WITH HOT BITUMEN. WHERE NECESSARY EXISTING SURFACE TO BE SAW CUT TO PROVIDE A NEAT VERTICAL EDGE. RADII BETWEEN 10M AND 20M TO BE LAID USING 600MM UNITS. 20MM UPSTAND AT VEHICLE CROSSOVERS.

DENOTES NEW KERBS & EDGINGS

HB2 PRECAST CONCRETE 'HALF BATTERED' KERB 125X255, BS REF 'HB2' SET WITH 125MM FACE UNLESS OTHERWISE INDICATED/TIED IN WITH EXISTING TO INCLUDE TAPER KERBS 125 X 255/150, BS REF 'DL1, DR1'.

PROPOSED HB2 KERBS AND ASSOCIATED TRANSITION/DROPPER KERBS EITHER SIDE OF THE PROPOSED PEDESTRIAN CROSSING ARE AVAILABLE FROM SUPPLIERS, WITHOUT THE NEED TO CUT KERBS.

EF PRE-CAST CONCRETE 'FLAT TOP' EDGING 200X50, BS REF 'EF', FLUSH WITH FOOTWAY SURFACE.

BN DROPPED KERB CONSISTING OF 'PRECAST' CONCRETE 'BULL NOSE' KERB 125 X 150, BS REF 'BN', KERB SET FLUSH OR 6MM UPSTAND

TACTILE PAVING

450X450X80 CONCRETE 'BUFF' COLOURED TACTILE PAVING FLAGS
50MM 4:1 SAND/CEMENT BED
200MM TYPE 1 GRANULAR SUB-BASE MATERIAL TO CLAUSE 803
TACTILE PAVING SHALL BE INSTALLED IN ACCORDANCE WITH DEPARTMENT TRANSPORT REGIONS DOCUMENT 'GUIDANCE ON THE USE OF TACTILE PAVING SURFACES'. TACTILE INLAYS SHALL BE PROVIDED WHERE NECESSARY AT ALL EXISTING/NEW INSPECTION COVERS/STATS EQUIPMENT.

EXISTING GULLY GRATING AND FRAME TO BE REMOVED TO TIP AND POT FILLED WITH MIX ST2 CONCRETE TO BELOW FORMATION LEVEL.

PRECAST CONCRETE STREET GULLY 450MM DIA X 900MM TO BS 5911 BS EN 124 WITH DUCTILE IRON HINGE GULLY GRATE AND 100MM FRAME WITH ENCAPSULATING GRATING TO EN 124 D400 SINGLE PIECE HINGED. LOCATION AND NATURE OF SEWER TO BE CONFIRMED ON SITE PRIOR TO COMMENCING ANY DRAINAGE WORKS. CONTRACTOR TO ENSURE THAT NO OBLIQUE TURNS ARE MADE IN ALL GULLY CONNECTIONS AND ADJUST CONNECTIONS WHERE NECESSARY TO THE SATISFACTION OF THE LA ENGINEER.

EXISTING GULLY TO REMAIN.

PRIOR TO CONSTRUCTION THE CONTRACTOR IS TO SURVEY/PROOF AND IF NECESSARY CLEAR EXISTING SURFACE SEWERS/TAILPIPES TO CONFIRM PIPE ALIGNMENTS AND PREVENT ANY OBLIQUE CONNECTIONS WITH EXISTING PIPEWORK.

1. ALL ADOPTABLE SEWERS AND ASSOCIATED WORKS ARE TO COMPLY FULLY WITH "SEWERS FOR ADOPTION" 7TH EDITION. ALL DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE ON-SITE DRAWINGS PRIOR TO UNDERTAKING ANY WORKS AND ANY DISCREPANCIES WITH BOUNDARIES, FENCELINES, EARTHWORKS OR OTHERWISE REPORTED IMMEDIATELY TO THE ENGINEER PRIOR TO WORKS COMMENCING.

2. ALL HIGHWAY AND DRAINAGE WORKS TO BE TO ADOPTABLE STANDARDS AND SHALL COMPLY FULLY WITH THE LOCAL AUTHORITY SPECIFICATION, APPROVED STANDARD DETAILS AND THE RELEVANT SECTIONS OF THE DESIGN MANUAL FOR ROADS AND BRIDGES, SPECIFICATION FOR HIGHWAY WORKS AND BRITISH STANDARDS. CONTRACTOR TO ENSURE POSITIVE DRAINAGE TO ALL VALLIES PRIOR TO UNDERTAKING ANY PAVEMENT WORKS.

3. ANY PRIVATE WORKS ARE TO COMPLY FULLY WITH THE LATEST EDITIONS OF THE BUILDING REGULATIONS

4. ALL EXISTING STATIONS, INVERT LEVELS AND DRAINAGE NETWORK TO BE CHECKED BY THE CONTRACTOR AT THE START OF WORKS AND ANY DISCREPANCIES NOTIFIED TO THE ENGINEER. ALL LEVELS ARE BASED ON TOPOGRAPHICAL SURVEY INFORMATION PROVIDED BY OTHERS. ANY DISCREPANCIES BETWEEN THIS AND OTHER DRAWINGS TO BE REPORTED TO THE ENGINEER PRIOR TO CONSTRUCTION

5. ALL MATERIALS TO BEAR THE RELEVANT B.S.KITEMARK AND COMPLY FULLY WITH THE SPECIFICATIONS. ALL MATERIALS TO BE AGREED WITH THE OVERSEEING LOCAL AUTHORITY REPRESENTATIVE PRIOR TO ORDERING. ALL CONCRETE & CONCRETE PRODUCTS MUST USE SULPHATE RESISTANT CEMENT (UNLESS THE SITE INVESTIGATION REPORT PROVES THAT SULPHATE ATTACK FROM SOILS AND GROUNDWATER WILL NOT OCCUR).

6. ALL STATUTORY CONSENTS, OPENING NOTICES ETC. AS REQUIRED UNDER HIGHWAYS ACTS AND WATER INDUSTRIES ACTS, ARE TO BE OBTAINED BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF THE WORKS (UNLESS OTHERWISE STATED). ALL WORKS ARE TO BE INSPECTED BY L.A., NHBC OR STATUTORY AUTHORITY AS APPLICABLE.

7. CONTRACTOR TO MAKE ADVANCE ALLOWANCE FOR THE MANAGEMENT AND COORDINATION OF STATUTORY UNDERTAKERS DIVERSIONS WITHIN THEIR PROGRAMME OF WORKS. PRESENCE OF STATUTORY UNDERTAKERS EQUIPMENT IN THE HIGHWAY SHOULD BE VERIFIED BY THE CONTRACTOR ON SITE PRIOR TO STARTING ANY WORKS. THE LOCATION OF STATUTORY PLANT SHOWN ON ANY PLANS IS INDICATIVE ONLY AND SHOULD NOT BE RELIED UPON FOR THE LOCATION OF ANY PIPEWORK OR CABLING. THE CONTRACTOR SHOULD CONFIRM THE LOCATION OF ALL STATS PLANT BY HAND DUG TRIAL TRENCHES PRIOR TO COMMENCING ANY WORKS. ALLOWANCE FOR THE PRESENCE OF ALL STATS APPROPRIATE PROTECTION / DIVERSION MEASURES (INCORPORATING SPLIT DUCT AND 150MM CONCRETE SURROUND OR SIMILAR STATUTORY APPROVED METHOD) IS TO BE PUT IN PLACE BY THE CONTRACTOR (UNLESS STATED OTHERWISE). WHERE STATS EQUIPMENT ARE FOUND TO BE WITHIN THE AREA OF HIGHWAY WORKS.

8. PRIOR TO ORDERING THE CONTRACTOR IS TO AGREE ALL SIGN POSTS/LIGHTING COLUMN MATERIALS AND FINISHES WITH THE LOCAL AUTHORITY. ALL SIGNS TO COMPLY WITH BS EN 12899:2007 AND ITS NATIONAL ANNEX BS EN 12899-1:2007 AND THE TRAFFIC SIGNS REGULATIONS AND GENERAL DIRECTIONS 2002. ALL SIGNS ARE TO BE APPROVED PRIOR TO ORDERING. CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE PROVISION OF ALL REQUIRED EQUIPMENT AND ELECTRICAL FEEDS TO LIGHTING AND ANY SIGNALS PRIOR TO WORKS COMMENCING. CONTRACTOR TO MAKE ALLOWANCE FOR ANY LEAD-INS WITHIN THEIR PROGRAMME.

9. ALL ROADMARKINGS TO BE LAID IN ACCORDANCE WITH THE REQUIREMENTS OF THE TRAFFIC SIGNS MANUAL CHAPTER 5, TRAFFIC SIGNS REGULATIONS AND GENERAL DIRECTIONS. ROADMARKING MATERIALS, LAYING AND PERFORMANCE TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF BS EN 1436.ALL ACCESS COVERS WITHIN THE VICINITY OF THE WORKS TO HAVE HIGH FRICTION COVERS AND AGREED WITH LA ENGINEER PRIOR OF ALL LINING AND COVERS TO SUIT ADJACENT SURFACING

10. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL ADVANCE NOTICES ARE IN PLACE AND TRAFFIC MANAGEMENT AGREED FOR THE WORKS PRIOR TO COMMENCING. THE CONTRACTOR IS TO MAKE ALLOWANCE FOR THE COORDINATION OF ALL ELECTRICAL WORKS AND EQUIPMENT FOR SIGNALS AND STREETLIGHTING WITHIN THEIR PROGRAMME OF WORKS

C.D.M. REGULATIONS 2015

IN LINE WITH THE ABOVE REGULATIONS WE ARE OBLIGED TO INFORM THE CLIENT OF THE RISKS THAT MAY BE ENCOUNTERED IN THE CONSTRUCTION OF THESE WORKS. WHEREVER POSSIBLE RISKS HAVE BEEN ELIMINATED FROM THE DESIGN. HOWEVER DUE TO THE VERY NATURE OF THIS TYPE OF WORK IT IS NOT POSSIBLE TO REMOVE ALL THE RISKS FROM THE DESIGN. WE WOULD ALSO RESPECTFULLY REMIND THE CLIENT OF HIS OBLIGATIONS TO TAKE ALL REASONABLE STEPS IN ENSURING THAT ONLY COMPETENT CONTRACTORS WHO HAVE THE SKILLS, KNOWLEDGE AND EXPERIENCE TO DEAL WITH THE RISKS ASSOCIATED WITH THIS PROJECT AT TENDER STAGE AS TO THE MANNER IN WHICH THEY WILL DEAL WITH THE ELEMENTS OF RISK INVOLVED IN THIS TYPE OF WORK AND IN PARTICULAR THOSE HIGHLIGHTED BY CROFT BELOW:-

1. TRENCH EXCAVATIONS IN EXCESS OF 1.2M DEEP.
2. UNPROTECTED EDGES OF EXCAVATIONS TO PREVENT PEOPLE, MATERIALS AND VEHICLES FALLING INTO EXCAVATION.
3. GUARDING OF EXCAVATIONS OUTSIDE WORKING HOURS TO PREVENT UNAUTHORISED ACCESS.
4. WORKING ADJACENT TO MADE OR STRUCTURES.
5. CONFINED SPACE OPERATIONS.
6. DEALING WITH EXISTING SERVICES.
7. TRAFFIC MANAGEMENT ON EXISTING HIGHWAYS AND PROTECTION OF SITE PERSONNEL AND MEMBERS OF THE PUBLIC.
8. EMERGENCY PROCEDURE TO BE FOLLOWED IN EVENT OF ACCIDENT OR EMERGENCY.
9. METHOD OF WORKING WHERE CONTAMINATED GROUND IS PRESENT ON SITE.
10. CONFIRMATION WILL BE REQUIRED THAT ALL OPERATIVES ARE ADEQUATELY TRAINED, COPIES OF RELEVANT TRAINING CERTIFICATES TO BE SUPPLIED.
11. ANY CONSTRUCTION PERSONNEL, INCLUDING OPERATIVES INTENDING TO CONSTRUCT THE DESIGNS SHOWN ON THESE DRAWINGS SHOULD CONFIRM THAT THEY
HAVE BEEN REGULARLY AND THOROUGHLY BRIEFED BY THE PRINCIPAL CONTRACTOR ON ALL HEALTH AND SAFETY MATTERS AND HAVE HAD SIGHT OF:

I) THE FULL DESIGNERS AND CONTRACTORS RISK ASSESSMENTS AND RISK REGISTERS.
II) THE CONTRACTORS CONSTRUCTION HEALTH AND SAFETY PLAN
III) THE CONTRACTORS CONSTRUCTION METHOD STATEMENTS.

THE ABOVE LIST IS BY NO MEANS EXHAUSTIVE BUT IT DOES HIGHLIGHT OPERATIONS THAT PRESENT A RISK TO CONTRACTORS AND THE GENERAL PUBLIC.

WARNING-PRESENCE OF EXISTING STATS EQUIPMENT IN THE VICINITY OF THE WORKS

PRESENCE OF STATUTORY UNDERTAKERS EQUIPMENT IN THE HIGHWAY SHOULD BE VERIFIED BY THE CONTRACTOR ON SITE PRIOR TO STARTING ANY WORKS. THE LOCATION OF STATUTORY PLANT SHOWN ON ANY PLANS IS INDICATIVE ONLY AND SHOULD NOT BE RELIED UPON FOR THE LOCATION OF ANY PIPEWORK OR CABLING. THE CONTRACTOR SHOULD CONFIRM THE LOCATION OF ALL STATS PLANT BY HAND DUG TRIAL TRENCHES PRIOR TO COMMENCING ANY WORKS. ALLOWANCE FOR THE PRESENCE OF ALL STATS APPROPRIATE PROTECTION / DIVERSION MEASURES (INCORPORATING SPLIT DUCT AND 150MM CONCRETE SURROUND OR SIMILAR STATUTORY APPROVED METHOD) IS TO BE PUT IN PLACE BY THE CONTRACTOR (UNLESS STATED OTHERWISE). WHERE STATS EQUIPMENT ARE FOUND TO BE WITHIN THE AREA OF HIGHWAY WORKS.

REV	DETAILS	DRAWN	CHECKED	DATE

CLIENT:
CASTLE GREEN HOMES

PROJECT:
STANSTY CHAIN ROAD,
WREXHAM
(WREXHAM CB COUNCIL)

DRAWING TITLE:
S278 CONSTRUCTION MATERIALS

SCALES:
1:250 @ A0

DRAWN:	CHECKED:	DATE:
LB	JC	MAY 25

Eddisons
340 Deansgate
Manchester
M3 4LY
Email: info@pcrofts.co.uk
Tel: 0161 837 7380
Web: www.eddisons.com/services/transport-planning

DRAWING NUMBER: 4813-D002
REVISION: -

Eddisons

C:\Users\Leon.Blythe\OneDrive - Begbies Traynor Group\Desktop\GA Work\Stansty\S278 Stansty Chain Road, Wrexham Mastercopy (4813).dwg