


Arrays by array height			
Color	Values from	Values to	# Arrays
	-10.00	0.00	1
	0.00	0.10	1
	0.10	0.20	0
	0.20	0.30	0
	0.30	0.40	1
	0.40	0.50	1
	0.50	0.60	3
	0.60	0.70	9

Tables with "0 / 0 Type" Posts (166 Nos)

Tables with "200 / 0 Type" Posts (5 Nos)

Tables with "400 / 200 Type" Posts (8 Nos)

Wrexham A&B Total 179 Nos Tables

Note-1: Pile coordinates has been set in accordance with 3D topographic coordinates. During site application, first and last row of each tables shall be marked on ground by surveyor.

Note-2: "Hatches with different colours" indicate that on those tables panels are lack of ground clearance due to small hills or pits on location for each marked table. Local earthworks should be carried out related locations. No earth movement will be undertaken in the archeological area.

Note-3: "Cyan Cross Lines" indicate that on those tables East-West slopes are higher than ±15°.

Note-4: The tables marked with 'Blue Rectangle' are the tables that are located in the hollow or bump due to the East-West slope and may cause problems.

Description

	WREXHAM A 2P24 T-4 >> VP-25-229_2Vx24x2P_A0_GENERAL ASSEMBLY(AREA A)
	WREXHAM B 2P24 T-5 >> VP-25-229_2Vx24x2P_A0_GENERAL ASSEMBLY(AREA B)
	WREXHAM A 2P12 T-6 >> VP-25-229_2Vx12x2P_A0_GENERAL ASSEMBLY(AREA A)
	WREXHAM B 2P12 T-7 >> VP-25-229_2Vx12x2P_A0_GENERAL ASSEMBLY(AREA B)
	Fence
	Parsel

Project Description

DC Power	Module Type:	Total Module
-	JINKO SOLAR N TYPE BIFACIAL	7.680
AC Power	Inverter / DC BOX Type	Total INV Number
-		

Detail of the Assembly Structure

Table Details

2P24 (141 Table) , 2P14 (38 Table)

Orientation	Tilt	Row spacing	String size
South	20°	-	24 Module/string

Tischplanung

Preliminary

Project name:

Wrexham A-B

Drawing number:	Date:	Processor:	Examiner:
A09B0C0	23.07.2025	Eren Gültekin	Eren Gültekin
Latitude: -		Longitude: -	
Sun angle: -		Date and time of the simulation:	

VERGO ENERJİ SİSTEMLERİ