

Map 5 Construction Detail

All trees within the development boundary to be felled (outside bird nesting season and under supervision of bat worker)

Concrete kerb to be constructed along edge of public highway. Specification to be agreed with Highways department before work commences

New batters created by the excavation of the loading bay/ site access to be stable and planted with birch and hazel transplants at irregular spacing

Surface of loading bay and new access onto highway to be stoned with imported MOT crushed stone

Area to be sown with grass seed of appropriate mix

Height of wall and adjoining land to be reduced in height to provide sightlines as shown on Map 4

Levelled area on which timber will be stacked

Timber extraction track to start from this point once route has been determined and permissions sought

Levelled area on which to stack timber



1:250

OS MasterMap © Crown copyright 2022