MEMORANDUM

From:	Chief Officer, Environment & Technical	**To:**	Chief Officer Economy & Planning
		FAO:	Sarah Brett
Our Ref:	ET/DC/PP/P/2025/0761	**Your Ref:**	P/2025/0761
Date:	10/11/2025		

TOWN AND COUNTRY PLANNING ACT 1990

PROPOSAL: RHYDDHAU AMOD 3 (SAMPLAU), 5 (HALOGIAD), 7 (BIODDIOGELWCH), 14 (GOLEUADAU), 15 (CYNLLUN RHEOLI TRAFFIG ADEILADU), 16 (DULL AMGÁU) A 17 (TIRLUNIO)CANIATÂD CYNLLUNIO P/2023/0746 / DISCHARGE OF CONDITIONS 3 (SAMPLES), 5 (CONTAMINATION), 7 (BIODIVERSITY) 14 (LIGHTING), 15 (CONSTRUCTION TRAFFIC MANAGEMENT PLAN), 16 (MEANS OF ENCLOSURE) AND 17 (LANDSCAPING) OF PLANNING PERMISSION P/2023/0746

LOCATION: LAND WEST OF PENDIL, LLANGOLLEN ROAD, ACREFAIR, WREXHAM, LL14 3RS

I refer to your consultation / email dated 15/10/2025 in respect of the above.

CONDITION 14 - (LIGHTING)

The submitted Site Plan (Drg. No. R0.1.004 Rev C) indicates the proposed re-location of the existing lighting column. Having discussed this further with our Street Lighting Engineer, the existing column will be relocated to a position approximately half way between the existing column position and the eastern boundary limit. The LHA understand the applicant is liaising with our Street Lighting Section who will carry out the required modifications.

CONDITION 15 - (CONSTRUCTION TRAFFIC MANAGEMENT PLAN)

Comments from WCBC Traffic Section:-

Section 3.0, Para 3.2 of the CTMP states material for the site can be unloaded from the access at the front of the property. The trades can then park on the adjacent car park, which has ample parking facilities. **This is a traffic sensitive road and has parking restrictions, therefore they cannot unload from the access at the front of the site, also the car park is public and they have no guarantee that there will be available parking.**

The LHA therefore need further details on deliveries, as it can't be done on the highway and parking, the contractor can't presume there will be parking in the public car park

Supplementary Notes

The applicant's attention should be drawn to item nos. 1, 2, 3, 4 & 5 of the supplementary notes.



On behalf of Chief Officer, Environment & Technical

Appendix

Highways Development Control Standard Advisory Note

In the interests of maintaining highway safety, and to avoid obstruction of the public highway (in contravention of the Highways Act), The Applicant is advised to coordinate with the highway authority at highwayroadworks@wrexham.gov.uk in advance of commencement of the development/works with respect to:

1. *Skip, scaffolding, hoarding or A frame/signage (Permit required for these items, if on the public highway);*
2. *Use of a parking space for a set down/delivery area;*
3. *Record a dilapidation survey of the adjacent carriageway prior to commencement (to avoid being ask to repair damage by the Applicant whilst carrying out their works);*
4. *If any lane closure or obstruction of the highway is required for a crane or similar;*
5. *Protection against dust and debris blowing onto the public highway*
6. *Construction traffic parking locally avoiding nuisance to others;*
7. *If the Applicant's scope of work includes new apparatus in the highway, such as new mains services then a Section 50 licence will be required. Insurances and demonstration of competency to carry out works in the public highway will be required.*
8. *Lowering of kerbs or minor pavement alterations require Section 184 agreement. Insurances and demonstration of competency to carry out works in the public highway will be required.*
9. *A section 278 agreement works agreement is required for more significant alterations to the existing highway*
10. *Any temporary works affecting traffic lights, [pedestrian/cycle road crossings, or bus stops require pre-planning and permits;*
11. *For applications with a private driveway (either existing or proposed) connecting onto the public highway, the following conditions of approval apply:*

    - *No surface water from the applicants site should be allowed to drain onto the public highway,*
    - *The first 5m* minimum (for residential property) should be hard paved, avoiding gravel or loose chippings form spreading.*
    - *No gate should be built in a location where it would result in a car obstructing the highway whilst being unlocked, and it should not swing out and over a pavement or any other part of the highway.*

    **The hard paved length and set back if required is subject to the applicants proposed vehicular length*

The applicants should allow a minimum of 4 weeks' notice for any of the above standard requirements, and 6-8 weeks for lane closures & road closures (lead times may change without notice subject to workload and complexity). Any works involving Trunk roads should be coordinated separately and directly with the North & Mid Wales trunk Road Agency. For larger sites with a significant impact upon the highway, a Construction Traffic Management Plan will be required.