N

Cyclone 8 extractor fans

Wall mounted, ducting in ensuite ceiling void

ducting in ceiling void

Store Room
11.1m2

E/S

Bathroom for Bed 03, 04 & 06

Acoustic wall lining as defined in sound report

Doorway blocked up and made good

New stud partition

Acoustic wall lining as defined in sound report

E/S

Kitchenette

New stud partition

Acoustic wall lining as defined in sound report

Wall mounted, ducting in ensuite ceiling void

Bedroom-03
14.7m2

Doorway blocked up and made good

Bedroom-04
19.8m2

up

Landing

First floor plan 1:50

Proposed

HDS ARCHITECTURAL SERVICES
HDS Architectural Services, The Foundry,
15 Yorke Street, Wrexham
LL13 8LW
Tel (01978) 345250
www.hdsarchitectural.co.uk

Project;
67 King Street, Wrexham, LL11 1HR

Title;	**Scale (A3);**
08-Proposed First floor plan	1:50
Dwg No;	**Date;**
KS/PD/08	27.01.25

Revision;
Rev A - Amend layout following meeting with conservation officer - 30-04-25
Rev B - Amendments requested by conservation officer - 07-05-25
Rev-C Noise report recommendations added 18.06.25
Rev E - Remove 2 No Bedrooms - 06-11-25