N

PIV Input diffuser

Cyclone 8 extractor fans

PIV system to be installed in the loft,
the input diffuser located in the hallway allowing
positive airflow through the buiding.

Ducting in ceiling void

Bedroom-07
11m2

New stud partition

E/S

E/S

New opening

Doorway blocked
up and made good

Bedroom-05
14.7m2

Landing

Acoustic wall lining as defined in sound report

Bedroom-06
19.7m2

Wall mounted, ducting in ensuite ceiling void

W-03-01 Secondary glazing
to be installed

W-03-02 Secondary glazing
to be installed

Second floor plan 1:50

Proposed

HDS ARCHITECTURAL SERVICES
HDS Architectural Services, The Foundry,
15 Yorke Street, Wrexham
LL13 8LW
Tel (01978) 345250
www.hdsarchitectural.co.uk

Project;
67 King Street, Wrexham, LL11 1HR

Title;
09-Proposed
Second floor plan

Scale (A3);
1:50

Dwg No;
KS/PD/09

Date;
27.01.25

Revision;
Rev A - Amend layout following meeting with conservation officer - 30-04-25
Rev B - Amendments requested by conservation officer - 07-05-25
Rev-C Noise report recommendations added 18.06.25