MEMORANDUM

From:	Chief Officer, Environment & Technical	**To:**	Chief Officer Economy & Planning
		FAO:	Tyler Fox
Our Ref:	ET/DC/PP/P/2026/0207	**Your Ref:**	P/2026/0207
Date:	15/04/2026		

TOWN AND COUNTRY PLANNING ACT 1990

PROPOSAL: DYMCHWEL YR ESTYNIAD PRESENNOL, ADNEWYDDU'R ESTYNIAD PRESENNOL A'R ESTYNIAD CEFN UNLLAWR / DEMOLITION OF EXISTING EXTENSION, RENOVATION OF EXISTING EXTENSION AND SINGLE STOREY REAR EXTENSION

LOCATION: PICKHILL FARM, PICKHILL, CROSS LANES, WREXHAM, LL13 0UL

I refer to your consultation / email dated 09/04/2026 in respect of the above.

General

The proposed development comprises modifications to an existing 3 bed dwelling to an extended 4 bed dwelling.

Access

The proposed development is located on the B5130 Holt Road which is a classified, rural road subject to a 40mph speed limit.

Based on typical speeds of 40mph, any proposed / existing access would require visibility splays of 2.4 x 120m in both directions measured to the nearside edge.

Visibility from the existing access serving the farm is acceptable providing splays in excess of 2.4 x 120m in both directions.

Parking & Turning Provision

Adequate parking & turning provision appears available within the site curtilage.

The LHA have no objections to the proposed development and recommend any permission includes the following condition:-

CONDITION

ZJ41 **GENERAL LAYOUT**

026R Prior to first use of the development the site shall be laid out in strict accordance with layout plan(s) No. **@@@**

Supplementary Notes

The applicant's attention should be drawn to item nos. 1, 2, 3, 4 & 5 of the supplementary notes.

Appendix

Highways Development Control Standard Advisory Note

In the interests of maintaining highway safety, and to avoid obstruction of the public highway (in contravention of the Highways Act), The Applicant is advised to coordinate with the highway authority at highwayroadworks@wrexham.gov.uk in advance of commencement of the development/works with respect to:

1. *Skip, scaffolding, hoarding or A frame/signage (Permit required for these items, if on the public highway);*
2. *Use of a parking space for a set down/delivery area;*
3. *Record a dilapidation survey of the adjacent carriageway prior to commencement (to avoid being ask to repair damage by the Applicant whilst carrying out their works);*
4. *If any lane closure or obstruction of the highway is required for a crane or similar;*
5. *Protection against dust and debris blowing onto the public highway*
6. *Construction traffic parking locally avoiding nuisance to others;*
7. *If the Applicant's scope of work includes new apparatus in the highway, such as new mains services then a Section 50 licence will be required. Insurances and demonstration of competency to carry out works in the public highway will be required.*
8. *Lowering of kerbs or minor pavement alterations require Section 184 / 171 agreement. Insurances and demonstration of competency to carry out works in the public highway will be required.*
9. *A section 278 agreement works agreement is required for more significant alterations to the existing highway*
10. *Any temporary works affecting traffic lights, [pedestrian/cycle road crossings, or bus stops require pre-planning and permits;*
11. *For applications with a private driveway (either existing or proposed) connecting onto the public highway, the following conditions of approval apply:*

    - *No surface water from the applicants site should be allowed to drain onto the public highway,*
    - *The first 5m* minimum (for residential property) should be hard paved, avoiding gravel or loose chippings form spreading.*
    - *No gate should be built in a location where it would result in a car obstructing the highway whilst being unlocked, and it should not swing out and over a pavement or any other part of the highway.*

    **The hard paved length and set back if required is subject to the applicants proposed vehicular length*

The applicants should allow a minimum of 4 weeks' notice for any of the above standard requirements, and 6-8 weeks for lane closures & road closures (lead times may change without notice subject to workload and complexity). Any works involving Trunk roads should be coordinated separately and directly with the North & Mid Wales trunk Road Agency. For larger sites with a significant impact upon the highway, a Construction Traffic Management Plan will be required.

KW Edwards

Contracts & Engineering Manager

On behalf of Chief Officer, Environment & Technical