NORTH

PLANTING KEY

No peat based compost should be used during planting (although some shrubs may arrive in peat base)
Chemicals should be used sparingly and if only absolutely necessary

BORDER / SHRUB PLANTING	pot size	height	Specification
Calluna Vulgaris - heather	9cm	10-20cm	Bushy
Erica cinerea - heather	9cm	10-20cm	Bushy
Vaccinium myrtillus - bilberry	2ltr	60-80cm	Bushy - 2 breaks
Cotoneaster frigidus	3ltr	40-60cm	Branched - 2 breaks
Berberis darwinii	3ltr	30-40cm	Bushy - 4 breaks
Vibernum bodnantense	3ltr	40-60cm	Branched - 3 breaks
Mahonia sp	3ltr	40-60cm	Bushy - 2 breaks
Pyracantha	3ltr	40-60cm	leader with several laterals : 4 breaks

LANDSCAPING LEGEND

Existing hedgerow retained
fence with hawthorn, blackthorn, beech or yew planted behind

1200mm high brick wall with piers
hawthorn, blackthorn, beech or yew planted in front

1200mm high post and rail fence with hawthorn, blackthorn, beech or yew planted behind

Existing tree retained

English Oak
Quercus Ruber
10L Pot 150 - 200cm

Rowan Ash
Sorbus Aucuparia
10L Pot 150 - 180cm

Agricultural land

Grassed Area

Porcelain Tiles

Granite Setts

Tarmac Driveway

hawthorn, blackthorn, beech or yew

Recycling / Bin Stores

Secure Bike Store

RIBA Chartered Practice
MARK WILLACY ARCHITECTS

client
MR. NATHAN CUNNINGHAM

job
PROPOSED REPLACEMENT DWELLING
GAMFORD FARM, GAMFORD LANE, ROSSETT

title
PROPOSED HARD AND SOFT LANDSCAPING

scale	date	job no.	drawing no.	rev
1:250@A1	20 FEB '26	MSW208	ST02	

A :- Penmon House, 76 Hoole Road, Chester CH2 3NL
T :- +44 (0)1244 853891 / +44 (0)7973 322953
E :- mark@markwillacyarchitects.co.uk
www :- markwillacyarchitects.co.uk