

Notes

Hardstanding 5x3m
Dropped kerb required
Gravel 2x1.3m to top of on-plot for water dispersal
Gravel strip to R/H side between on-plot & existing fence
Link path 1x1.2m at top of on -plot to existing path
Planning permission required

Check for Virgin Media cables in footway and garden areas

KEY

- Precast Concrete BN Kerb 125 x 150mm
- Precast Concrete DL1/DR1 Kerb
- Precast Concrete EBN Kerb

HARDSTANDING SPECIFICATION

Surface Course, Dense Bitumen Macadam, 10mm nominal size,depth 40mm
Binder Course, Dense Bitumen Macadam, 20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 300mm

FOOTWAY SPECIFICATION

Surface Course, Dense Bitumen Macadam, 10mm nominal size,depth 20mm
Binder Course, Dense Bitumen Macadam, 20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 150mm

All setting out to be agreed with WCBC prior to commencing works on site

WREXHAM COUNTY BOROUGH COUNCIL
Housing Services,
Housing and Public Protection Department,
Ruthin Road,
Wrexham.
LL13 7TU
Tel: (01978) 315300 Fax: (01978) 315355

Project: 82 Stryt Las, Rhos, Wrexham LL14 2HF			
Detail: Proposed Hardstanding and Dropped Kerb			
Drawn By: MB	Date: April 2026	Checked By:	
Scale: NTS	Project No:	Dwg No: 01	Rev: Preliminary

82 Stryt Las, Rhos