
New 6ft x 8ft timber shed to replace existing



Existing garage/outbuilding to be adapted for incidental domestic use ancillary to Achill

New 900mm x 600mm limestone paving slabs, laid in brick pattern to fall towards existing surface water drain

New linear drain to existing surface water drain

T1

T2

Grassed area

B

A

Achill

Adjoining property

Grassed area

Brick wall to be rendered in rough cast lime render between points A and B.

New cobblestone apron

New 900mm x 600mm limestone paving slab wheel tracks with limestone gravel infill to form parking area

Limestone paving



Nic holson Price Associates

Project	Achill
Author	LNJ
Checked By	TJN
Drawing Description	Plan view as proposed (external)
Drawing Number	DWG14
Date	May 2026
Scale	1mm : 100mm @ A3