

Notes

Hardstanding 5.0m x 3.2m
AcoDrain and soakaway required

It is prohibited to remove hedges or trees during the nesting season, (Approx mid-March to September)

Check for Virgin Media cables in footway and garden areas

KEY

- Double gravel board with timber fence over
- Precast Concrete BN Kerb 125 x 150mm
- 600x900x63mm precast concrete paving flag laid vertical
- Precast Concrete EBN Kerb

HARDSTANDING SPECIFICATION

Surface Course, Dense Bitumen Macadam, 10mm nominal size,depth 40mm
Binder Course, Dense Bitumen Macadam, 20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 200mm

FOOTPATH SPECIFICATION

Surface Course, Dense Bitumen Macadam, 10mm nominal size,depth 20mm
Binder Course, Dense Bitumen Macadam, 20mm nominal size,depth 60mm
Sub-base, Granular Sub-base Type1 ,depth 150mm

All setting out to be agreed with WCBC prior to commencing works on site

WREXHAM COUNTY BOROUGH COUNCIL
Housing Services,
Housing and Public Protection Department,
Ruthin Road,
Wrexham.
LL13 7TU
Tel: (01978) 315300 Fax: (01978) 315355

Project: 15 Pen Y Graig Road			
Detail: Proposed On Plot and Drop Kerb			
Drawn By: AJ	Date: July 2026	Checked By:	
Scale: A3@1:100	Project No:	Dwg No: 02	Rev: Preliminary

15 Pen Y Graig Road