Rainwater goods at Plas Newydd - update

There is a mix of very short sections of cast iron, together with large sections of upvc RWG at Plas Newydd. It was originally proposed to replace the RWG system at Plas Newydd with new, half round, Alumasc Heritage guttering all-round, on rise and fall brackets. The use of Alumasc was considered an appropriate compromise due to the costs of cast iron and the financial outlay required to restore this at risk grade II* building.

On reflection, and following feedback from the Conservation Officer, cost alone cannot be used to justify materials on a grade II* building. It is now proposed to use cast iron RWG at Plas Newydd. It is proposed to slightly increase the capacity of the gutters and downpipes to deal with the increasingly inclement Welsh weather.

The proposed elevation plans as well as the HIA has been updated to reflect the change.